

U.S. 101 MP 142.48 HARLOW CREEK (WDFW ID 990548): Preliminary Hydraulic Design Report



**Eleanor Bartolomeo PE, Project Manager
Stream Design Engineer
FPT20-07379
Natural Systems Design**

**Aaron Lee, Staff Hydraulic Engineer EIT
FPT20-05353
Natural Systems Design**

**Scott Katz, Project Geomorphologist
FPT20-35854
Natural Systems Design**

Americans with Disabilities Act (ADA) Information

Materials can be made available in an alternative format by emailing the WSDOT Diversity/ADA Affairs Team at wsdotada@wsdot.wa.gov or by calling toll free: 855-362-4ADA (4232). Persons who are deaf or hard of hearing may contact that number via the Washington Relay Service at 7-1-1.

Title VI Notice to Public

It is Washington State Department of Transportation (WSDOT) policy to ensure no person shall, on the grounds of race, color, national origin, or sex, as provided by Title VI of the Civil Rights Act of 1964, be excluded from participation in, be denied the benefits of, or be otherwise discriminated against under any of its federally funded programs and activities. Any person who believes his/her Title VI protection has been violated may file a complaint with WSDOT's Office of Equal Opportunity (OEO). For Title VI complaint forms and advice, please contact OEO's Title VI Coordinator at 360-705-7082 or 509-324-6018.

Contents

1	Introduction	1
2	Watershed and Site Assessment.....	4
2.1	Watershed and Land Cover	4
2.2	Geology and Soils	7
2.3	Floodplains	9
2.4	Site Description	9
2.5	Fish Presence in the Project Area.....	9
2.6	Wildlife Connectivity	10
2.7	Site Assessment.....	11
2.7.1	Data Collection.....	11
2.7.2	Fish Habitat Character and Quality.....	26
2.8	Geomorphology	28
2.8.1	Reference Reach Selection	28
2.8.2	Channel Geometry	31
2.8.3	Sediment.....	36
2.8.4	Vertical Channel Stability.....	39
2.8.5	Channel Migration	42
2.8.6	Riparian Conditions, Large Wood, and Other Habitat Features.....	43
3	Hydrology and Peak Flow Estimates	44
4	Hydraulic Analysis and Design	46
4.1	Model Development	46
4.1.1	Topographic and Bathymetric Data	46
4.1.2	Model Extent and Computational Mesh	46
4.1.3	Materials/Roughness.....	49
4.1.4	Boundary Conditions	52
4.1.5	Model Run Controls.....	57
4.1.6	Model Assumptions and Limitations	58
4.2	Existing-Conditions Model Results	58
4.3	Natural-Conditions Model Results	65
4.4	Channel Design.....	71

4.4.1	Floodplain Utilization Ratio	71
4.4.2	Channel Planform and Shape	72
4.4.3	Channel Alignment	74
4.4.4	Channel Gradient	75
4.5	Design Methodology	75
4.6	Future Conditions: Proposed 15-Foot Minimum Hydraulic Opening	75
4.7	Water Crossing Design	81
4.7.1	Structure Type	81
4.7.2	Minimum Hydraulic Opening Width and Length.....	81
4.7.3	Freeboard	82
5	Streambed Design	85
5.1	Bed Material.....	85
5.2	Channel Complexity	86
5.2.1	Design Concept.....	86
6	Floodplain Changes	88
6.1	Floodplain Storage	88
6.2	Water Surface Elevations	88
7	Climate Resilience	91
7.1	Climate Resilience Tools.....	91
7.2	Hydrology	91
7.3	Climate Resilience Summary	91
8	Scour Analysis	92
8.1	Lateral Migration.....	92
8.2	Long-term Aggradation/Degradation of the Riverbed.....	92

Figures

Figure 1: Vicinity map	3
Figure 2: Land cover map.....	5
Figure 3: 1939 aerial photograph of project site	6
Figure 4: 1996 aerial photograph of project site	6
Figure 5: Geologic map	8
Figure 6: Mainstem Harlow Creek Upstream from Confluence	12
Figure 7: Substrate of Mainstem Harlow Creek Upstream from Confluence.....	13
Figure 8: Large Woody Material (LWM) from historic logging	13
Figure 9: Mid channel stump in UNT to Harlow Creek Left Bank	14
Figure 10: Typical gravels upstream of stump.....	14
Figure 11: Typical UNT channel view with approximately 3 foot high banks.....	15
Figure 12: Abundant LWM suggesting historical logging activities	16
Figure 13: Stream conditions downstream of confluence.....	16
Figure 14: Floodplains downstream of confluence.....	17
Figure 15: Large undefined bowl	17
Figure 16: LWM accumulation near exit of pool.....	18
Figure 17: Substrate downstream of LWM near exit of pool	18
Figure 18: Stream conditions between LWM and inlet	19
Figure 19: Bank erosion near culvert inlet.....	20
Figure 20: Culvert inlet.....	20
Figure 21: Culvert outlet	21
Figure 22: Brush and debris in channel.....	22
Figure 23: Reference reach	23
Figure 24: Reference reach substrate and pebble count location.....	24
Figure 25: Reference reach substrate (gravelometer for scale)	24
Figure 26: Typical channel conditions downstream of reference reach.....	25
Figure 27: Channel incising and undercut bank.....	25
Figure 28: WS drop over sedge	26
Figure 29: Typical segment of reference reach on June 25, 2021. Flow direction is from right to left of photo.....	29
Figure 30: Reference reach	30
Figure 31: Existing cross-section examples.....	32
Figure 32: Location of bankfull width measurements	33
Figure 33: BFW 1 from the second site visit on June 25, 2021	35
Figure 34: BFW 2 from the second site visit on June 25, 2021	35
Figure 35: BFW 3 from the second site visit on June 25, 2021	36
Figure 36: Upstream sediment distribution from 2021 pebble count.....	37
Figure 37: Downstream substrate with gravelometer for reference from first site visit on July 28, 2020	38
Figure 38: Downstream sediment size distribution.....	39
Figure 39: Watershed-scale longitudinal profile with average slopes.....	41

Figure 40: Watershed-scale long profile with polynomial equilibrium slope line	42
Figure 41: Basin map.....	45
Figure 42: Existing-conditions computational mesh with underlying terrain	47
Figure 43: Natural-conditions computational mesh with underlying terrain.....	48
Figure 44: Proposed-conditions computational mesh with underlying terrain	49
Figure 45: Spatial distribution of roughness values in SRH-2D existing-conditions model	50
Figure 46: Spatial distribution of roughness values in SRH-2D natural-conditions model	51
Figure 47: Spatial distribution of roughness values in SRH-2D proposed-conditions model	52
Figure 48: Channel downstream boundary condition input.....	53
Figure 49: Channel downstream normal depth rating curve.....	54
Figure 50: Roadside drainage downstream boundary condition input	54
Figure 51: Roadside drainage downstream normal depth rating curve.....	55
Figure 52: HY-8 Culvert parameters for existing conditions simulation	55
Figure 53: Location of boundary conditions for the existing-conditions model.....	56
Figure 54: Location of boundary conditions for the natural-conditions model	56
Figure 55: Location of boundary conditions for the proposed-conditions model.....	57
Figure 56: Model controls.....	57
Figure 57: Locations of cross sections used for results reporting for existing-, natural-, and proposed-conditions models.....	60
Figure 58: Longitudinal profile stationing for existing, natural, and proposed conditions	60
Figure 59: Existing-conditions water surface profiles.....	62
Figure 60: Typical downstream existing-conditions channel cross section (STA 1+94).....	62
Figure 61: Typical upstream existing-conditions channel cross section (STA 4+31)	63
Figure 62: Existing-conditions 100-year velocity map with cross-section locations	64
Figure 63: Natural-conditions water surface profiles	67
Figure 64: Typical downstream natural-conditions channel cross section (STA 1+94)	67
Figure 65: Cross section (STA 2+65) through removed structure for natural conditions.....	68
Figure 66: Typical upstream natural-conditions channel cross section (STA 4+31)	69
Figure 67: Natural-conditions 100-year velocity map with cross-section locations.....	70
Figure 68: Locations of FPW measurements	72
Figure 69: Design cross section.....	73
Figure 70: Proposed versus existing cross section.....	74
Figure 71: Proposed-conditions water surface profiles.....	78
Figure 72: Section through proposed structure (STA 2+65)	78
Figure 73: Proposed-conditions 100-year velocity map. Flow direction is from bottom to top of figure..	79
Figure 74: Proposed-conditions 2080 predicted 100-year velocity map. Flow direction is from bottom to top of figure.	80
Figure 75: Conceptual layout of habitat complexity.....	87
Figure 76: Existing and proposed 100-year water surface profile comparison.....	89
Figure 77: 100-year water surface elevation change. Flow direction is from bottom to top of figure.....	90

Tables

Table 1: Percent of Basin Coverage by Land Cover Class.....	4
Table 2: Native fish species potentially present within the project area	10
Table 3: Bankfull width estimates from hydraulic model and WSDOT topographic survey.....	34
Table 4: Bankfull width measurements from first site visit on July 28, 2020	34
Table 5: Bankfull width measurements from second site visit on June 25, 2021.....	36
Table 6: Upstream sediment properties from 2021 pebble count.....	37
Table 7: Downstream sediment properties	39
Table 8: Peak flows for Harlow Creek at U.S. 101 MP 142.48	44
Table 9: Manning's n-value hydraulic roughness coefficient values used in the SRH-2D model	50
Table 10: Hydraulic results for existing conditions within main channel	61
Table 11: Existing-conditions velocities including floodplains at select cross sections	65
Table 12: Hydraulic results for natural conditions within main channel.....	66
Table 13: Natural-conditions velocities including floodplains at select cross sections	70
Table 14: Flood-prone widths and floodplain utilization ratio results	71
Table 15: Hydraulic results for proposed conditions within main channel	77
Table 16: Proposed-conditions velocities including floodplains at select cross sections.....	80
Table 17: Velocity comparison for proposed 15-foot wide structure opening	82
Table 19: Comparison of observed and proposed streambed materials	85
Table 20: Report summary.....	93

1 Introduction

To comply with United States et al. vs. Washington et al. No. C70-9213 Subproceeding No. 01-1 dated March 29, 2013 (a federal permanent injunction requiring the State of Washington to correct fish barriers in Water Resource Inventory Areas [WRIAs] 1–23), the Washington State Department of Transportation (WSDOT) is proposing a project to provide fish passage at the United States Highway 101 (U.S. 101) crossing of Harlow Creek, tributary to the Queets River at Mile Post (MP) 142.48. This existing structure on U.S. 101 has been identified as a total fish barrier by the Washington Department of Fish and Wildlife (WDFW) and WSDOT Environmental Services Office (ESO) (site identifier [ID] 990548) and has an estimated 3,600 linear feet (LF) of habitat gain.

In accordance with the injunction, and in order of preference, fish passage should be achieved by (1) avoiding the necessity for the roadway to cross the stream, (2) use of a full-span bridge, or (3) use of the stream simulation methodology. WSDOT evaluated the crossing using the unconfined bridge design methodology; this method was necessary because the stream is unconfined.

The crossing is located in Grays Harbor County on U.S. Highway 101, five miles east of the intersection with Clearwater Road, Washington, and 19 miles west of Lake Quinault, Washington and the U.S. 101 crossing of the Quinault River, in WRIA 21. The highway runs in an east–west direction at this location and the crossing is about 5.6 miles upstream from the confluence of Harlow Creek with the Queets River based on the National Hydrography Database. Harlow Creek generally flows from southeast to northwest beginning about 3,900 feet (ft) upstream of the U.S. 101 crossing (see Figure 1 for the vicinity map).

The proposed project will replace the existing 4-foot-diameter corrugated metal pipe (CMP) culvert measuring 74.1 ft in length with a structure designed to accommodate a minimum hydraulic opening of 15 feet. A specific structure type will be determined during future phases of the design. The proposed structure is designed to meet the requirements of the federal injunction using the unconfined bridge design criteria as described in the 2013 WDFW *Water Crossing Design Guidelines* (WCDG) (Barnard et al. 2013). This design also meets the requirements of the WSDOT *Hydraulics Manual* (WSDOT 2019).

This culvert crossing is located within the Quinault Indian Nation Reservation. As a result, some information readily available for other culvert crossings is not available. For example, the Federal Emergency Management Agency (FEMA) has not performed a flood hazard analysis in this area, and the United States Geological Survey (USGS) has not done a soils analysis. This Preliminary Hydraulic Design (PHD) Report was prepared using all available information, and other sources of information have been used in place of those generally used in other PHD reports.

The draft report of the preliminary hydraulic design (PHD) was prepared by HDR, Inc. (HDR) in 2020. WSDOT received review comments on the Draft PHD from Washington Department of Fish and Wildlife (WDFW) and Quinault Tribe (Tribe). As part of Kiewit’s Coastal-29 Team of the US 101/SR 109 Grays Harbor/Jefferson/Clallam, Remove Fish Barriers Project under a Progressive Design-Build (PDB) contract between Kiewit and WSDOT, Natural Systems Design (NSD) reviewed the draft PHD report, updated the

hydraulic modeling and design, addressed WDFW and Tribe comments, and prepared the Draft Final PHD report. Responses to WDFW and Tribe comments are included in Appendix J.

DRAFT




Figure 1: Vicinity map

2 Watershed and Site Assessment

The existing site was assessed in terms of watershed, land cover, geology, floodplains, fish presence, wildlife, and geomorphology. This assessment was performed using desktop research including aerial photo analysis, resources such as USGS, FEMA, and WDFW, and past records including field surveys, maintenance records, and fish passage evaluations.

2.1 Watershed and Land Cover

Harlow Creek drains into the left bank of the Queets River approximately 5 miles downstream of the U.S. 101 culvert outlet. Harlow Creek consists of approximately 5.8 miles of stream length. Watershed area was measured at MP 142.48 as 200 acres (0.31 square mile) using Arc Hydro. This is the watershed for the MP 142.48 crossing only, not the entirety of Harlow Creek. The watershed is relatively flat with an average slope of 4.7 percent; none of the basin is characterized by slopes greater than 30 percent. According to StreamStats, the basin is 41 percent covered by canopy (USGS 2016). The basin is densely forested and interspersed with logging activities.

Figure 2 shows the National Land Cover Database (NCLD) map. The breakdown of land cover within the watershed is in Table 1. The basin is primarily evergreen forest.

Table 1: Percent of Basin Coverage by Land Cover Class

Land cover class	Basin coverage (percent)
Evergreen Forest	76.4
Low intensity developed	5.5
Scrub/shrub	16.4
Mixed forest	0.9
Herbaceous	0.5
Open space developed	0.5




Figure 2: Land cover map

Aerial photographs of land cover dating from 1939 to 1996 accessed through the ArcGIS Living Atlas show the advent of logging activities at the site. The 1939 photo in Figure 3 shows that little to no logging or development was present in the area. However, by the 1996 photo in Figure 4, logging activities and development have cleared the forest in some areas.




Figure 3: 1939 aerial photograph of project site



Figure 4: 1996 aerial photograph of project site

2.2 Geology and Soils

Geologic units in the watershed are summarized from 1:100,000 quadrangle mapping by USGS (Gerstel and Lingley 2000) and obtained from the Washington State Department of Natural Resources (DNR) Geologic Information Portal. The geology of the watershed for this project site is comprised of the geologic units described below and referenced in Figure 5. The entire basin is mapped as alpine glacial drift (Qapwt(2m)) and (Qapwo(2)).

- **Qapwt(2m):** Pleistocene Age, alpine glacial till, pre-Wisconsinan (Pleistocene alpine glacial drift)
 - Undifferentiated till and outwash; outwash consists of sand and gravel with lacustrine silt and clay; till is locally capped by loess; clasts are composed primarily of lithofeldspathic and feldspatholithic sandstone and basalt
- **Qapwo(2):** Pleistocene Age, alpine glacial outwash, pre-Wisconsinan (Pleistocene alpine glacial drift)
 - Sand and gravel composed of lithofeldspathic and feldspatholithic sandstone and basalt derived from the core of the Olympic Mountains

The Natural Resources Conservation Service (NRCS) Web Soil Survey cannot be used to summarize soils and geology at this crossing because the project is located on tribal lands and as a result no data are available.




Figure 5: Geologic map

2.3 Floodplains

The project site is located on the Quinault Indian Nation Reservation and is not included in the Flood Insurance Study (FIS) for Grays Harbor County. A separately published FIS for the Quinault Indian Nation Reservation was not available at the time of preparing the PHD. Thus, the project is not located within a regulatory Special Flood Hazard Area, (with a 1 percent or greater annual chance of flooding in any given year) based on the available data. The crossing is located well outside of the floodplain of the Salmon River, the nearest river with a mapped floodplain, located less than two miles east of Harlow Creek. The crossing is also outside of the Queets River floodplain. No other information on flooding history of the site such as maintenance or historical records has been provided.

2.4 Site Description

The existing culvert at U.S. 101 MP 142.48 was documented by WDFW having a 0 percent passability rating because of a water surface drop at the culvert outlet. The outlet of the pipe drops 0.9 foot to the channel bed downstream of the existing crossing, making it impassable to fish (WDFW 2014, WDFW 2019). In addition, the structure has a slope of 3.28 percent according to the WDFW database report (the WSDOT survey measures it as 2.8 percent; see Section 2.7.2), a second criterion for 0 percent passage (WDFW 2019). Comments on the WDFW form identify that inside the culvert, the velocity was measured as 14 feet per second (ft/s) and the stream plunges onto riprap below the outlet. The WDFW Fish Passage and Diversion Screening Inventory (FPDSI) documents unresolved fish passage problems both upstream and downstream of the crossing (WDFW 2014). Further detail regarding the extent and location of these problems is not provided in this report, though it is known that there is a downstream fish passage barrier at MP 142.68 that will be addressed and evaluated in its respective PHD report. Additionally, another barrier downstream with WSDOT Site ID 990178 is being removed, and the new structure is currently in construction. The total length of habitat gain for this crossing is 3,600 feet (WDFW 2014).

This culvert is not considered to be a chronic environmental deficiency. Maintenance records obtained by WSDOT do not indicate previous issues at the existing crossing.

2.5 Fish Presence in the Project Area

The Statewide Washington Integrated Fish Distribution (SWIFD) (2020), as well as StreamNet (2020), document biological evidence of coho salmon (*Oncorhynchus kisutch*) spawning and rearing in the lower reaches of Harlow Creek approximately 4.5 miles downstream of the project area. These databases do not have fish use data for the upper reaches of Harlow Creek in the project vicinity; however, upper Harlow Creek does meet the physical criteria for the presence of coho salmon, steelhead, searun cutthroat trout, and resident trout (WDFW 2014, WDFW 2019). A downstream habitat survey conducted by WDFW in 2014 documents physical evidence of spawning and rearing habitat just downstream of the culvert (WDFW 2014). Coho use in Harlow Creek downstream of the project area is also reported in the WRIA 21 Queets-Quinault stream catalog (Williams and Phinney 1975).

The Queets River is documented to contain all five Pacific salmon species as well as steelhead and bull trout (Quinault Indian Nation 2011, SWIFD 2020, WDFW 2020, StreamNet 2020). The small substrate

(D50 = 1.3 inches), and limited number of deep pools and complex cover in Harlow Creek, however, may preclude Chinook (*Oncorhynchus tshawytscha*) from using this stream. Bull Trout have more specific habitat requirements than most other salmonids, in particular they require cold water (46 °F or below) for spawning and egg incubation, and abundant in-stream cover for rearing (Rieman and McIntyre 1993). They typically spawn and rear in the cold, clear tributaries in the upper portions of watersheds, and therefore are not expected to be present in this area of Harlow Creek since it is low in the Queets watershed.

Rearing juvenile coho and steelhead may disperse upstream to reaches close to the project crossing. Steelhead that inhabit the Queets River are part of the Olympic Peninsula distinct population segment (DPS) and are not currently listed under the Endangered Species Act (ESA). The WDFW online fish passage database does not list any impassable barriers on the mainstem Harlow Creek between the downstream reaches where coho are documented, and upstream where the project is located; though as mentioned above, unresolved fish passage problems are noted in the 2014 report that may or may not have been corrected at the time of the writing of this report. Coastal cutthroat trout (*Oncorhynchus clarkii clarkii*) are also widespread throughout small streams in Washington and are likely also present in Harlow Creek. They prefer the uppermost portions of these streams and may exhibit several life history patterns. They can be anadromous and rear in streams for two to three years or be resident and remain entirely in freshwater (Wydoski and Whitney 2003).

Table 2 provides a list of salmonid species that potentially occur in Harlow Creek and that could be affected by the culvert crossing.

Table 2: Native fish species potentially present within the project area

Species	Presence (presumed, modeled, or documented)	Data source	ESA listing
Coho salmon (<i>Oncorhynchus kisutch</i>)	Presumed (documented downstream)	SWIFD 2020, WDFW 2020, Quinault Indian Nation 2011	Not warranted
Olympic Peninsula DPS^a steelhead (<i>Oncorhynchus mykiss</i>)	Presumed (documented in Queets River)	SWIFD 2020, WDFW 2020, Quinault Indian Nation 2011	Not warranted
Coastal cutthroat (<i>Oncorhynchus clarkii clarkii</i>)	Presumed	SWIFD 2020, Quinault Indian Nation 2011	Not warranted

a. DPS = distinct population segment.

2.6 Wildlife Connectivity

The one-mile segment that contains MP 142.48 ranked medium priority for Ecological Stewardship and Low priority for Wildlife-related Safety. Adjacent segments to the north and south ranked medium for

Ecological Stewardship and Low for Wildlife-related Safety. WSDOT has determined that in order to be eligible for a habitat connectivity analysis, fish barrier correction projects must either be located in or adjacent to a high priority road segment or have been requested by a project team member for analysis. Thus, this project is not eligible.

2.7 Site Assessment

The following sections describe the existing conditions of Harlow Creek as observed during the site visits conducted on July 28, 2020 and June 25, 2021.

2.7.1 Data Collection

WSDOT conducted a topographic survey in March 2020. The survey extends 240 feet upstream of the culvert, 230 feet downstream of the culvert, with a total roadway survey length of 660 feet. Survey information generally includes locations of stream channels and overbank areas along the channel.

During the preliminary design phase of the project, HDR visited the project site on July 28, 2020, to measure the bankfull width (BFW) and collect pertinent information to support the basis of design. This section describes field observations collected during the July 28, 2020 and June 25, 2021 site visits of Harlow Creek from upstream to downstream. The main findings of the field reports are summarized in the subsections below and the full reports can be found in Appendix B.

NSD conducted the second site visit on June 25, 2021, along with Osborn Consulting (OCI) and Kiewit staff, to identify the WSDOT survey limits in the field and verify observations and findings from the 2020 site visit. Previous BFW measurement locations were reoccupied and remeasured, as were pebble counts. Concurrence was reached on a BFW of 10.3 feet by WDFW and QIN on August 9, 2021. BFW determination is discussed in detail in Section 2.8.2.Existing Conditions

The existing structure is a 74.1-foot-long, circular, corrugated steel, 4-foot-diameter culvert. From the WSDOT survey, the culvert has a gradient of 2.8 percent with the inlet invert elevation at 351.6 feet and the outlet invert elevation at 349.5 feet. As-built drawings for this crossing were provided by WSDOT; however, they contained minimal information pertaining to Harlow Creek and the existing structure at MP 142.48. As described above in Section 2.4, the creek crossing has high velocities (approximately 14 ft/s) and unresolved fish passage problems both upstream and downstream. The crossing is listed in WDFW's database as being a total barrier for fish and blocking biologically significant habitat. The barrier reduces fish access to rearing habitat by 37,040 square feet (SF). Species expected to benefit from removing and replacing this culvert include coho, steelhead, sea run cutthroat, and resident trout. Local constraints are not apparent from aerial photos, topographic survey, or WDFW field reports. The culvert runs perpendicular to the road and the stream begins to run parallel to the road downstream of the crossing. No obvious signs of maintenance activity were observed, and no local constraints or infrastructure were observed.

Upstream

The upstream area observed during the site visit consisted of three different reaches, from upstream to downstream: (1) mainstem Harlow Creek upstream of the confluence with the unnamed tributary (UNT), (2) UNT left bank, and (3) mainstem Harlow Creek from the confluence to the culvert inlet. Each

reach is described below, and Figure 30 shows the stream network within the extent of the surveyed limits.

1. Mainstem Harlow Creek Upstream of Confluence with UNT

The detailed topographic survey includes 50 feet of Harlow Creek above the confluence with the UNT. The upper reach of Harlow Creek is narrow and marshy, with a substrate entirely made up of silt and fines (Figure 6).



Figure 6: Mainstem Harlow Creek Upstream from Confluence

Sedges and brush are abundant on both banks. The banks are low, approximately 1 foot in height, and the channel is not well defined (Figure 7).



Figure 7: Substrate of Mainstem Harlow Creek Upstream from Confluence

The active floodplains are accessible, flat, and narrow; they are also terraced and slope up to a second floodplain that appears accessible only under extreme flood events. The large accumulation of logs in the upper mainstem channel are most likely the result of historic logging activities (Figure 8). At the confluence of the left bank UNT and mainstem, an accumulation of logs and fine sediment deposits were observed.




Figure 8: Large Woody Material (LWM) from historic logging

2. UNT to Harlow Creek Left Bank

Detailed topographic survey of the UNT to Harlow Creek Left Bank extends 40 feet upstream of the confluence with Harlow Creek. At this location, a large stump lies across the channel with ferns and shrubs growing out of it (Figure 9). Flow goes under and around the stump.



Figure 9: Mid channel stump in UNT to Harlow Creek Left Bank

The channel substrate at this location is made up of fines, gravels, and some cobbles deposited upstream of the stump (Figure 10).



Figure 10: Typical gravels upstream of stump

Downstream of the stump, the substrate is composed primarily of fines and organic material. The UNT channel is more defined than the upper reach of Harlow Creek. Both left and right banks are

approximately 3 feet in height and the floodplains appear inaccessible (Figure 11). As the UNT approaches the confluence with Harlow Creek, flow follows the undulating bed surface under and around LWM and a large stump.



Figure 11: Typical UNT channel view with approximately 3-foot-high banks

3. Mainstem Harlow Creek from Confluence to Culvert Inlet

At the approximate location where the UNT and Harlow Creek meet, an island is present in the middle of the Harlow Creek channel. Trees grow out of the island in the middle. Small gravels and a few cobbles are present on either side of the island. There is a multitude of wood in the channel, all indicative of historical logging activities (Figure 12). Both banks are approximately 3 to 4 feet in height and are near vertical, and the channel substrate is dominated by the presence of fines.



Figure 12: Abundant LWM suggesting historical logging activities

Where the flow converges on the downstream side of the island, there is a large log jam consisting of logs associated with historic timber harvest. Downstream of the jam, the channel narrows to approximately 10 feet wide. The substrate in this area is mostly fines with some gravels and cobbles. Sedge and brush grow in and over the channel in this reach. The bank slopes are gradual and about 2 feet tall and are composed primarily of silt and fines material. Stands of young trees grow on the banks. The banks are undercut, and the floodplains are flat and accessible (Figure 13 and Figure 14). Logs help form and shore up the banks periodically.



Figure 13: Stream conditions downstream of confluence



Figure 14: Floodplains downstream of confluence

Farther downstream, there is a pool approximately 30 to 40 feet in diameter (Figure 15). LWM from logging activities is present in the pool and racked up at the downstream end towards the right bank (Figure 16). This wood appears to be stable and somewhat decomposed, with no evidence of recent movement. The substrate of the pool is entirely fines, and the floodplains are accessible to streamflow.



Figure 15: Large undefined bowl



Figure 16: LWM accumulation near exit of pool

Downstream of the LWM at the exit of the pool, there is a large deposit of gravels and cobbles (Figure 17). The largest bed material found in this location was 4.5 inches in diameter.



Figure 17: Substrate downstream of LWM near exit of pool

The substrate from this section downstream to the culvert inlet is primarily gravels. Approximately 50 feet upstream of the culvert inlet, LWM recruited naturally from the banks is present in the channel and forming accumulations that span the channel between both banks (Figure 18). Valley occlusion has led to some areas where logs are quite dense and accumulating soils, supporting tree and shrub growth, which the stream flows and pools beneath. The area is characterized by a complex of multiple flow paths and sloughs.



Figure 18: Stream conditions between LWM and inlet

The channel shape in this area consists of short vertical banks that slope up towards a flat floodplain. The banks are undercut in the proximity of the culvert and confine the channel in a straight, entrenched planform (Figure 19). Flow contraction due to an undersized culvert is likely driving localized channel bed and bank erosion at the existing inlet. Naturally recruited logs provide a degree of bank stability in the area between the racked-up wood and the culvert. On the right bank near the culvert, a small side channel enters the stream. It likely carries floodplain flow from upstream to this location. There is LWM present in the side channel.



Figure 19: Bank erosion near culvert inlet

The culvert itself is a 4-foot-wide CMP mitered to slope (Figure 20). The culvert inlet is perched approximately 4 inches above the channel bed.



Figure 20: Culvert inlet

The planform in the upstream segment of MP 142.48 overall is characterized by a meandering channel with a slope of approximately 1 to 2 percent outside of culvert backwater influence. The segment also has defined banks interspersed with accumulations of LWM from both past logging influences and natural recruitment that cause occasional pools and gravel deposits to form.

Downstream

At the outlet of the culvert, there is an approximate 6-inch drop from the culvert apron below to riprap which lines the channel bed (Figure 21). The existing metal apron is failing due to corrosion and past undermining at the transition to the channel. Riprap is present in the channel for 15 feet downstream of the culvert.



Figure 21: Culvert outlet

The right bank is about 3 to 4 feet tall, while the left bank is lower with an accessible inset floodplain surface. Stands of young trees and ferns grow on the banks. Some undercutting of the channel bank is present at a bend downstream of the rip rap. Small debris and brush are racked up after this bend, throughout the whole of the downstream reach. All debris within the channel appears to be a result of natural recruitment, though the pieces and accumulations are not stable enough to provide a lasting influence on channel form or processes (Figure 22).



Figure 22: Brush and debris in channel

The reference reach begins downstream of the racked LWM roughly 45 feet downstream from the culvert outlet. (Figure 23). The left bank is about 1 to 2 feet tall, and the right bank is about 2 to 3 feet tall. The left bank floodplain is flat before sloping up to the roadway. The right floodplain is moderately sloped. Roots of trees form the banks periodically on both sides of the channel. The channel itself is 4 to 5 feet wide, and entrenched within its near vertical banks, owing to the influence of the undersized culvert opening. This channelized section is armored and relatively stable, as evidenced by the establishment of moss on top of streambed cobbles.



Figure 23: Reference reach

All three BFWs were taken through this section of stream. BFW measurements and photographs are provided in Section 2.8.2. The channel substrate is gravels and cobbles, and a pebble count was performed here as well (Figure 24 and Figure 25). Trees are present on the banks and in the floodplains, but there is little brush. The reference reach selected is most likely influenced by the culvert discharge, but a superior reference reach was not found due to the incised channel banks throughout the channel both upstream and downstream.



Figure 24: Reference reach substrate and pebble count location



Figure 25: Reference reach substrate (gravelometer for scale)

Downstream of the reference reach, the channel shape changes to become narrower and deeper with inaccessible floodplains (Figure 26). Both banks are 3 to 4 feet in height and show signs of erosion due to channel incision (Figure 27). The banks are vegetated with brush and trees, and the substrate is gravels and cobbles.



Figure 26: Typical channel conditions downstream of reference reach



Figure 27: Channel incising and undercut bank

Approximately 30 feet before the end of the survey extents, there is a 6-inch water level drop over sedges and sediment present in the channel (Figure 28). At the very downstream end of the survey, the

channel changes shape again, widening and aggrading with limited connections to a small wetland complex off the right bank. The wetland complex includes areas of ponded water, multiple main channel connections, and stands of emergent wetland vegetation such as *Carex* spp.



Figure 28: WS drop over sedge

The planform in the downstream reach of MP 142.48 overall is characterized by plane-bed morphology. The channel itself is flat without a defined thalweg, and the slope is approximately 2 percent.

2.7.2 Fish Habitat Character and Quality

Upstream of the US 101 crossing, Harlow Creek and its left bank UNT flow through a mature mixed forest consisting of alder (*Alnus rubra*), Western hemlock (*Tsuga heterophylla*), Douglas fir (*Pseudotsuga menziesii*), and western red cedars (*Thuja plicata*). There is a dense shrub understory with native species including evergreen huckleberry (*Vaccinium ovatum*), salmonberry (*Rubus spectabilis*), willows (*Salix* spp.), vine maple (*Acer circinatum*), salal (*Gaultheria shallon*), and sedges and ferns. The shrub understory is particularly dense at the upstream end of the surveyed reach where the mature tree canopy recedes back from the stream channel creating an open canopy. Downstream of the small island, the mature tree canopy covers and shades the stream, and the understory shrubs become much less dense. The mature forest and shrub cover provides good shading, nutrient inputs, and potential for LWM recruitment. LWM is important in western Washington streams in that it provides cover for fish and contributes to stream complexity, which is beneficial to salmonids.

There were many places where large logs and woody material were present within the stream channel and banks, and LWM was abundant throughout the upstream reach. There were over 50 significant pieces of LWM in the channel and on the banks, with several locations of log piles. These logs generally ranged in size from 8 to 36 inches in diameter and also included some rootwads. Much of this wood was perched above the wetted channel and not interacting with streamflow under low flow conditions. There is a large LWM accumulation that covers the stream channel near the downstream end of the reach. The abundant LWM provides cover, velocity refuge, and habitat complexity for fish throughout the upstream reach.

Generally, the upstream channel can be characterized by a complex of pools and small sloughs forced by riparian vegetation, LWM, and rootwads. Pools, and the transition areas between pools and riffles, are important habitat for adult and juvenile salmon, allowing them to rest and feed. The slow water of pools also allows the fish to rest and feed on invertebrates that accumulate there while the depth provides protection from predators as well as cooler water. Further upstream, the stream is narrower and shallower, and instream habitat is comprised predominantly of shallow glides and riffles with a few small pools associated with LWM. The water was colored dark brown with abundant tannins. Fish in western Washington often utilize waters that are tannic and are successful in rearing, growth, and reproduction in these areas.

The abundant LWM provides habitat complexity and cover for salmonids using this reach for rearing and migration, particularly during high flow periods; however, these functions are limited during summer low flows such as during the field visit where shallow water, LWM jams and pool isolation may impede juvenile fish movement through this reach. Spawning gravels are limited and the upstream reach does not provide much suitable salmon spawning habitat and will therefore primarily provide rearing opportunity for juvenile salmonids.

The downstream reach parallels the highway for the length of the field survey and the riparian corridor consists of a relatively narrow strip of mixed forest including western hemlock, Douglas fir, and alders. The right bank is located next to a large timber harvested area that has been replanted with young conifers, and the riparian corridor of mature trees is also restricted to a narrow strip. Although the mature tree cover along both banks provides good shading for the stream, the constricted riparian corridor limits potential LWM recruitment. LWM is much less abundant in the downstream reach than upstream. There were no pieces of significant LWM within the wetted channel except a 10-inch diameter conifer log across the top of bankfull about mid-reach. There was an area just downstream of the culvert that had many large branches and other smaller woody material in and across the channel. The shrub understory is abundant along both banks and consists of native species including vine maple, salmonberry, and willows.

The downstream channel is generally straight and lacks habitat complexity. It is predominantly riffle and glide habitat over small cobbles and fines, with very few pools or cover from LWM. A small scour pool along an undercut bank provides the only in-stream pool habitat in the downstream reach. However, a small complex of wetlands including ponded water and emergent wetland vegetation exists off the right bank with minimal connection to the main channel. This could serve as important water storage and overwintering refuge for migrating fish. In some areas, sedges and aquatic vegetation have grown within

the stream channel and were visible during the late-June field visit expressing low flow conditions. The substrate is dominated by fines at the downstream end of the surveyed reach. Suitable spawning habitat for the salmonids that inhabit the stream is lacking in the downstream reach. This reach is primarily suited to be a migratory corridor, particularly during periods of higher flows. Some limited rearing habitat is present, but the lack of connection with the adjacent wetlands as well as pools and habitat complexity reduce this function as fish do not have adequate resting areas or cover.

2.8 Geomorphology

Geomorphologic information provided for this site includes selection of a reference reach, the basic geometry and cross sections of the channel, stability of the channel both vertically and laterally, and various habitat features.

2.8.1 Reference Reach Selection

A section of stream approximately 45 feet downstream of the culvert (Figure 29 and 30) was chosen as the reference reach because it has the least amount of anthropogenic influences within the surveyed limits. This reach has an approximate average channel gradient of 1.5 percent. A pebble count was conducted at the reference reach. This reference reach was used primarily for proposed design channel shape and comparison to proposed hydraulic results throughout this Preliminary Hydraulic Design (PHD) Report, as the entire upstream reach was influenced by an unnatural density of LWM from historic logging activities. While the reference reach is not completely outside of the area of influence from the existing culvert and road prism, and shows signs of degradation, its selection is acceptable for BFW measurement and channel design.



Figure 29: Typical segment of reference reach on June 25, 2021. Flow direction is from right to left of photo.




Figure 30: Reference reach

2.8.2 Channel Geometry

Channel planform at this crossing is characterized by a meandering and undefined channel upstream with a much straighter and entrenched channel downstream. Upstream, two tributaries converge into a reach where flow is significantly influenced by the presence of several log jams and spreads onto an accessible floodplain at high flow events. The slope is approximately 2.2 percent (see Section 2.8.4). Downstream, the channel takes a sharp bend following the culvert outlet and flows parallel with the road prism within a single-threaded, plane-bed channel. The slope is approximately 1 to 2 percent. The reference reach is located from approximately STA 1+05 to STA 1+90. The cross-section geometry through the reference reach is used for design comparison, and the upstream longitudinal profile slope of 2.2 percent (Section 2.8.4) is used for the slope ratio design comparison.

Figure 31 shows typical detailed cross sections at the project site developed from the WSDOT survey: one upstream of the U.S. 101 crossing, one just upstream of the culvert, and one downstream of the culvert. The upstream-most cross section shown (STA 4+16) is narrow, with a wide, flat floodplain that is often wetted due to the abundance of LWM spreading flow out of the channel. The cross section immediately upstream of the culvert (STA 3+18) includes a large scour pool in front of the culvert as all flow converges at the culvert inlet approach. The downstream-most cross section shown (STA 1+56, in the reference reach) has the widest channel shape with a defined thalweg and terraced floodplains. The channel geometry within the reference reach (STA 1+56) provides the best-available reference cross section for the design of the proposed crossing to provide adequate depth at low-flows and an accessible floodplain surface near channel-forming flows.

The width-to-depth ratio is measured at the reference reach cross section at STA 1+56 and is approximately 6:1. The channel averages 1 to 1.5 feet deep. The channel evolution stage was evaluated in the reference reaches and estimated to be in Stage I of the Channel Evolution Model (Schumm et al. 1984).




Figure 31: Existing cross-section examples

Initial estimates of BFW were derived from two methods. First, using the existing-conditions model in SMS (described below in section 4), the 2-year flow top width was computed at three locations. At these same locations, the top of bank width was also measured based on the topographic survey provided by WSDOT (Figure 32, and listed in Table 3). BFW 2 is located in the identified reference reach and BFW 1 is immediately upstream; the detailed BFW cross sections are shown in Figure 32.

The average 2-year top width (modeled) is 10.9 feet, while the average top of bank width (surveyed) is 9.6 feet. The average of these two values results in an initial BFW estimate of 10.3 feet.

For comparison, a BFW was calculated based on the WCDG (Barnard et al. 2013) regression equation for high-gradient, coarse-bedded streams in western Washington. Using the basin area (0.31 square mile) and average mean annual precipitation (116.8 inches [in]/year) the regression equation estimates a BFW of 10.3 feet, the same value as the initial estimated BFW. The WCDG regression equation method BFW was not used to determine a design BFW but is provided for informational purposes and for comparison.




Figure 32: Location of bankfull width measurements

Table 3: Bankfull width estimates from hydraulic model and WSDOT topographic survey

BFW #	2-Year Top Width from Model (ft)	Top of Banks Width from Survey (ft)	Included in Design Average	Concurrence Notes
1 (STA 1+97)	9.2	10.7	Yes	WDFW and Tribe concur
2 (STA 1+32)	8.5	9.3	Yes	WDFW and Tribe concur
3 (STA 0+20)	14.9	10.2	Yes	WDFW and Tribe concur
Design average	10.9	9.6		
Overall design average	10.3			

During the first site visit conducted on July 28, 2020 three initial BFW measurements were taken in the field downstream of the crossing in the reference reach, see Table 4. The measurements ranged from 7.4 to 7.9 feet, resulting in an average width of 7.6 feet. See Appendix B for bankfull width measurement photos. Figure 30 shows the location of the respective three measurements.

Table 4: Bankfull width measurements from first site visit on July 28, 2020

BFW #	Width (ft)	Included in design average
1	7.9	No
2	7.4	No
3	7.5	No
Average	7.6	

A second site visit was conducted on June 25, 2021 to independently evaluate the BFW. Field measurements were taken at previously occupied transects in the reference reach according to vegetation, surface sediment, and topographical features. BFW measurements from the second site visit are shown in Figure 33, Figure 34, and Figure 35 which reoccupy BFW sites 1, 2, and 3 from the first site visit, respectively.



Figure 33: BFW 1 from the second site visit on June 25, 2021



Figure 34: BFW 2 from the second site visit on June 25, 2021



Figure 35: BFW 3 from the second site visit on June 25, 2021

A summary of BFW measurements from the second site visit listed in Table 5, which were taken at the same locations as the first site visit. The difference in measurements is attributed to inclusion of inset floodplain surfaces connected to the left bank at channel forming flows during the second site visit. Inundation of these accessible benches are typical for low-to-moderate grade streams with sinuous planforms and broad floodplains, such as Harlow Creek.

Table 5: Bankfull width measurements from second site visit on June 25, 2021

BFW #	Width (ft)	Included in design average	Concurrence notes
1	11.0	Yes	WDFW and Tribe concur
2	11.25	Yes	WDFW and Tribe concur
3	9.0	Yes	WDFW and Tribe concur
Average	10.4		

The average BFW from the second site visit is 10.4 feet, which validates the initial BFW estimate of 10.3 feet. WDFW and the Tribe performed individual site visits to measure BFWs and a concurrence meeting was held virtually on August 9, 2021 to agree on a design BFW of 10.3 feet.

2.8.3 Sediment

One pebble count was taken during the July 2020 site visit, approximately 45 feet downstream of the crossing within the reference reach with 300 particles. Two pebble counts of 100 particles each were taken during the June 2021 site visit, one upstream and downstream of the crossing. The upstream pebble count was taken approximately 120 feet upstream of the culvert inlet and the downstream pebble count occupied the 2020 pebble count location.

The results of the pebble count indicated that the bed material was composed primarily of fine and medium to coarse gravels and small cobbles. The cumulative distribution and pebble sediment sizes for

the upstream pebble count is provided in Table 6 and Figure 36. A photo of the downstream substrate is provided in Figure 37 with a gravelometer for reference. Table 7 and Figure 38 provides a summary of downstream pebble count data. The largest sediment size in the downstream reach observed was 10.1 inches (0.8 foot) in diameter.

Table 6: Upstream sediment properties from 2021 pebble count

Particle	Upstream Diameter (in)	Upstream Diameter (mm)
D₁₆	0.1	2.5
D₅₀	0.1	3.6
D₈₄	0.3	8.4
D₉₅	0.8	21.0
D₁₀₀	1.3	33.0




Figure 36: Upstream sediment distribution from 2021 pebble count



Figure 37: Downstream substrate with gravelometer for reference from first site visit on July 28, 2020

Table 7: Downstream sediment properties

Sediment Size	2020 Count		2021 Count	
	Diameter (in)	Diameter (mm)	Diameter (in)	Diameter (mm)
D₁₆	0.4	10.2	0.4	10.2
D₅₀	1.3	33.0	1.4	35.6
D₈₄	2.9	73.7	3.0	76.2
D₉₅	4.0	101.6	4.8	121.9
D₁₀₀	10.1	256.5	7.1	180.3




Figure 38: Downstream sediment size distribution

2.8.4 Vertical Channel Stability

A long channel profile was developed from 2020 WSDOT survey data and 2011 light detecting and ranging (LiDAR) data (Watershed Sciences 2011). Both data sets show the road embankment at the crossing locations. The channel profile (Figure 39) describes the channel bed approximately 2,000 feet upstream and 3,000 feet downstream from the project culvert and includes major landmarks along the tributary. Upstream of the survey extents and almost all the way through the survey, the slope is approximately 2.2 percent. Downstream of the survey, the slope averages approximately 1.5 percent. There is a private driveway crossing in this reach that appears as a bump on the LiDAR profile and may affect the stream slope. Below this, the tributary travels through the culvert at MP 142.68 (the next downstream WSDOT crossing) at an approximate slope of 0.8 percent for 500 feet. Farther downstream, the slope stays at approximately 1.5 percent for approximately 2,000 feet. The slopes and channel geometries within the survey extents are described in more detail in the paragraphs below.

The upstream channel is unconfined and undeveloped. The channel is characterized by the presence of several stable log jams captured in the survey. As a result, pools have formed, and flow spreads out into the floodplains throughout the upstream reach at presumably most high flow events. Additionally, the log jams have been decelerating the approach velocity of the flow and limiting degradation in the upstream reach. Starting at the upstream extents of the survey approximately 200 feet upstream of the culvert inlet, the channel has a slope of approximately 1.1 percent for approximately 50 feet and is made up of two separate tributaries that meet nearly 140 feet upstream of the culvert inlet. Approximately 50 feet below the confluence, the channel steepens to approximately 5 percent and continues until it reaches the upstream culvert inlet. There is potential for erosion at the upstream inlet of the culvert due to the floodplain flow converging with the main channel at the structure opening. Conditions leading to local contraction scour are likely to persist as long as the undersized structure remains but do not pose a long-term or reach-wide risk of vertical channel instability.

Downstream, the channel has both confined and unconfined stretches. From the culvert outlet to approximately 110 feet downstream, the channel is confined and entrenched within defined banks. At this point, the left bank becomes low and terraced and flow spills out into the floodplain, creating an unconfined channel. Throughout the entire downstream reach, the average slope of the surveyed extent is approximately 1 percent below the culvert outlet. The existing drop at the culvert outlet will be removed, including scour protection rock, in proposed conditions by daylighting the channel into the downstream bed elevations at a constant slope, this armored downstream reach is stable. Sediment supply, composed primarily of fines with gravel, is deposited near the existing log jams. Sediment yield potential within the basin may fluctuate with changes to land use and land cover but does not pose a significant risk of aggradation in the project reach.




Figure 39: Watershed-scale longitudinal profile with average slopes




Figure 40: Watershed-scale long profile with polynomial equilibrium slope line

2.8.5 Channel Migration

Channel migration was assessed primarily through field observations. The historical aerial imagery provides few insights on channel migration near the project site due to canopy cover. The upstream-most reach within the survey extents has its channels filled with an abundance of debris and wood from historical logging activities, including a wood accumulation that totals 60 feet in length. There are several accumulations formed by key pieces across the middle of the channel. The cumulative effect of the logjams are split flow paths, creation of broad floodplain surfaces, and deposition of fine sediment. Where wood is not present, a low flow channel is carved from unconsolidated fine sediment.

Significant bank erosion in the upstream reach is present in the approach channel to the culvert inlet, which is likely driven by flow contraction at high flow events. The straightened plane-bed planform of the approach reach is indicative of channel incision from elevated velocities rather than lateral channel migration.

Downstream, there are terraces activated at higher flows, but the channel itself is confined and there is a low risk for channel migration. The channel is largely straight with low sinuosity. Active bank erosion was observed on the right bank immediately downstream of the current culvert outlet, though the extent is localized to the outside meander bend. Given that the left bank floodplain bench is accessible

during approximate 1-year flow events to alleviate erosive energy in the main channel, the risk of channel migration in the project reach is low.

2.8.6 Riparian Conditions, Large Wood, and Other Habitat Features

Clearcutting of forests throughout the region over the past century has resulted in major changes to the riparian systems along most streams and has created smaller, and less diverse riparian corridors and reduced stability of stream systems. The forest surrounding the upstream reach is a mature mixed forest consisting of alder, Western hemlock, Douglas fir and some western red cedars. The surrounding conifer forested area is secondary growth from previous timber harvest. The shrub understory is particularly dense at the upstream end of the surveyed reach where the mature tree canopy recedes back from the stream channel creating an open canopy. Shrub species were dominated by native species including salmonberry, willows, vine maple, salal, and sword fern.

Abundant LWM was observed throughout the upstream reach. There were over 50 significant pieces of LWM in the channel and on the banks, with several locations of log piles and log jams. These logs generally ranged in size from 8 to 36 inches in diameter and included some rootwads. Approximately 50 feet upstream of the culvert, there is a large LWM accumulation that completely spans the channel. Multiple flow paths have been created in and around this accumulation with a large pool forming just upstream of it. This along with two other stable log jams located near the upstream extents of the survey, act to encourage bank overtopping during high flow events.

The downstream reach parallels highway 101 for the length of the field survey. The riparian corridor consists of a relatively narrow strip of mixed forest between the road prism and the stream including western hemlock, Douglas fir, and alder. The stream flows through a former timber harvested area and right bank riparian corridor is limited to a narrow strip approximately 30 feet in width by the edge of a relatively recent timber harvested cut-block with young, replanted conifer trees. Although the mature tree cover along both banks provides good shading for the stream, the constricted riparian corridor limits potential LWM recruitment. LWM is much less abundant in the downstream reach than upstream. There was only a single piece of significant LWM across the bankfull channel and a few areas with debris jams of branches and small material.

The downstream reach is composed of a straightened plane-bed channel with little habitat variability and devoid of deep pools.

No beaver activity was observed in the upstream or downstream reach.

3 Hydrology and Peak Flow Estimates

Harlow Creek is within an ungaged basin, with no long-term historical flow data available. A gaged basin with similar characteristics was not located. One previous hydrologic report was found for this basin; in 2017, a Basis of Design Report was written for U.S. 101 MP 146.85 Harlow Creek (WSDOT 2017). This report estimated a total drainage area of 3.97 square miles for the Harlow Creek watershed within the Quinault Reservation. Hydrology was analyzed using both the MGSFlood and USGS Regression equations methods; the USGS Regression equations were used because that method yielded more conservative flows. The USGS Regression equations (Mastin et al. 2016) for Region 4 were used to estimate peak flows at the U.S. 101 MP 142.48 crossing (Table 8). Inputs to the regression equation included basin size and mean annual precipitation. Harlow Creek at the crossing has a basin area of 0.31 square mile and a mean annual precipitation within the basin of 116.8 inches (PRISM Climate Group 2019). The basin was delineated from LiDAR data acquired from the Washington DNR LiDAR Portal (Watershed Sciences 2011) using Arc Hydro. The basin can be seen in Figure 40. Flows were calculated based on the watershed as a whole and divided into the left UNT and mainstem Harlow Creek based on their respective drainage basins. The 2-year peak flow was estimated to be 37.6 cubic feet per second (cfs) and the 100-year flow was estimated to be 110.0 cfs. Summer low flow conditions are unknown. Average standard error varied from 50.5 to 58.0 percent. Standard error was not applied to the flows used in the hydraulic modeling. Table 8 shows the calculated peak flows for Harlow Creek at U.S. 101 MP 142.48. For more information on how the 2080 predicted 100-year flow was determined see Section 7.2.

Table 8: Peak flows for Harlow Creek at U.S. 101 MP 142.48

Mean recurrence interval (MRI) (years)	USGS regression equation (Region 4) (cfs)			Regression standard error (percent)
	Left UNT	Harlow Creek	Total	
2	6.7	30.9	37.6	52.5
10	10.9	50.7	61.6	50.5
25	12.8	59.8	72.6	51.7
50	14.4	66.9	81.3	52.9
100	16.1	75.0	91.1	54.2
500	19.5	90.5	110.0	58.0
2080 predicted 100-year			113.2	NA




Figure 41: Basin map

4 Hydraulic Analysis and Design

The hydraulic analysis of the existing and proposed U.S. 101 MP 142.48 Harlow Creek crossing was performed using the U.S. Bureau of Reclamation's (USBR's) SRH-2D Version 3.2.4 computer program, a two-dimensional (2D) hydraulic and sediment transport numerical model (USBR 2017). Pre- and post-processing for this model was completed using SMS Version 13.0.12 (Aquaveo 2018).

Three scenarios were analyzed for determining stream characteristics for Harlow Creek with the SRH-2D models: (1) existing conditions with the 4-foot-diameter CMP, (2) natural conditions with the roadway embankment removed beyond the wetted extents and the channel graded to match the proposed grade, and (3) future conditions with the proposed 15-foot hydraulic opening.

4.1 Model Development

This section describes the development of the model used for the hydraulic analysis and design.

4.1.1 Topographic and Bathymetric Data

The channel geometry data in the model were obtained from the MicroStation and InRoads files supplied by the Project Engineer's Office (PEO), which were developed from topographic surveys performed by surveyors hired by WSDOT prior to March 13, 2020. The survey data were supplemented with LiDAR data (Watershed Sciences 2011). The LiDAR data were collected on the Quinault River Basin survey area for the Puget Sound LiDAR Consortium and the Quinault Indian Nation over approximately 370 square miles. Both airborne survey and ground survey were used to gather information for this deliverable.

Proposed channel geometry was developed from the proposed grading surface created by HDR. All survey and LiDAR information is referenced against the North American Vertical Datum of 1988 (NAVD88) and tied into the WSDOT grid using the NAD83 (1991 HARN) Horizontal Datum.

4.1.2 Model Extent and Computational Mesh

The hydraulic model upstream extents begin with the detailed survey data and start approximately 240 feet upstream of the existing culvert inlet. LiDAR data are stitched in as well to the east and west of the upstream survey extents to capture the unconfined channel. The hydraulic model downstream extents end with LiDAR beyond the survey data. The detailed survey data end approximately 230 feet downstream of the existing culvert outlet, measured along the channel centerline. LiDAR data continue for another 35 feet to accurately capture the flow leaving the model. In addition, LiDAR data are used to detail east and west of the downstream boundary condition because some flow exits the model in a different location from the surveyed downstream end of the reach.

The computational mesh elements are a combination of patched (quadrilateral) and paved (triangular) elements. Finer resolution was used in the channel (with the exception of large pools) and wherever else it was simple to use quadrilateral elements, while larger elements were used in the floodplain. The existing-conditions mesh covers a total area of 122,000 SF, with 5,575 quadrilateral and 17,979

triangular elements (Figure 41). The natural-conditions mesh, simulating what the creek would look like in its existing alignment without the roadway, covers a total area of 122,000 SF, with 5,492 quadrilateral and 18,283 triangular elements (see Figure 42). The proposed-conditions mesh covers a total area of 122,000 SF, with 5,059 quadrilateral and 18,313 triangular elements (see Figure 43).




Figure 42: Existing-conditions computational mesh with underlying terrain




Figure 43: Natural-conditions computational mesh with underlying terrain




Figure 44: Proposed-conditions computational mesh with underlying terrain

4.1.3 Materials/Roughness

Manning's n-values (roughness) were estimated based on site observations, aerial photography, and standard engineering values (Chow 1959) and are summarized below (Table 9). Roughness in the upstream and downstream floodplain are characterized by 0.12—heavy stands of timber, because of the densely forested landscape. The floodplain near the reference reach is characterized by 0.10, because the forest and shrubs in this location were less dense than elsewhere in the reach. The downstream

channel is 0.045, defining the main channel as clean and winding with some pools, shoals, weeds, and stones. The upstream channel is 0.06 because of the amount of LWM found in the channel. These values are listed in Table 9. Roughness values between existing and proposed conditions remained the same except for material inside the proposed structure and the downstream grading; see Figure 44 and Figure 45 for a spatial distribution of hydraulic roughness coefficient values.

Table 9: Manning's n-value hydraulic roughness coefficient values used in the SRH-2D model

Land cover type	Manning's n
Upstream Channel	0.06
Downstream Channel	0.045
Proposed Channel	0.060
Floodplains	0.12
Reference Reach Floodplains	0.10
Roadway	0.02




Figure 45: Spatial distribution of roughness values in SRH-2D existing-conditions model



Figure 46: Spatial distribution of roughness values in SRH-2D natural-conditions model



Figure 47: Spatial distribution of roughness values in SRH-2D proposed-conditions model

4.1.4 Boundary Conditions

Model simulations were performed using a quasi-steady inflow, with the design discharges (2-year to 500-year peak flow events) run to equilibrate within the model domain. External boundary conditions were applied at the upstream and downstream extents of the model domain and remained the same between the existing- and proposed-conditions runs. Two inflow hydrographs were specified at the upstream external boundary condition to represent the two tributaries, while two normal depth rating curves were specified at the downstream boundary: one at the channel exit, and one across the roadway for roadside drainage where flow is also leaving the existing-conditions model at higher flow events. The downstream normal depth boundary condition rating curve at the channel exit was developed within SMS using the existing terrain, assuming a downstream slope of 2.5 percent as measured from the survey and a composite roughness of 0.09. See Figure 46 for the channel

downstream boundary conditions and Figure 47 for the resulting rating curve. The downstream normal depth boundary condition rating curve at the roadside drainage was developed within SMS using the existing terrain, assuming a downstream slope of 2.0 percent as measured from LiDAR and a composite roughness of 0.12. See Figure 48 for the roadside drainage downstream boundary conditions and Figure 49 for the resulting rating curve. A sensitivity analysis on the downstream boundary condition was performed to obtain an accurate representation of the water surface profile and to determine if the boundary condition assumption affected hydraulics within the U.S. 101 crossing project extents. Model simulations were run for a sufficiently long duration until the results stabilized across the model domain.

An HY-8 internal boundary condition was specified in the existing-conditions model to represent the existing circular CMP culvert crossing. The existing crossing was modeled as a 4-foot-diameter circular pipe within HY-8. A Manning's roughness n -value of 0.024 was assigned to the culvert. The culvert was assumed to be unobstructed and free from any stream material within the barrel. See Figure 50 for the HY-8 boundary conditions. See Figure 51 for a map showing the location of each boundary condition in the existing-conditions model. A wall (no-slip) boundary condition was specified in the proposed-conditions model to represent flow inside the proposed structure.

See Figure 52 for a map showing the location of each boundary condition in the natural-conditions model.

The image shows a software dialog box titled "Populate". It contains several sections for configuring a rating curve:

- Options:**
 - Type: **Normal depth rating curve** (dropdown menu)
 - Ground Elevation Dataset: **select...** (button)
 - Units: **U.S. Units** (dropdown menu)
 - Composite Mannings N: **0.09** (text input)
 - Slope: **.025** (text input)
- Populate Flows:**
 - Min: **0** (text input)
 - Max: **120** (text input)
 - Delta: **5** (text input)
 - Add** (button)
- Flows (Q):** A list box containing the values **0**, **5**, and **10**. There are up and down arrow buttons on the right side of the list.
- Plot...** (button)
- At the bottom are **Help**, **OK**, and **Cancel** buttons.

Figure 48: Channel downstream boundary condition input




Figure 49: Channel downstream normal depth rating curve

Populate
✕

Options

Type: Normal depth rating curve

Ground Elevation Dataset: select... z

Units: U.S. Units

Composite Mannings N: 0.12

Slope: .02

Populate Flows

Min: 0

Max: 120

Delta: 5 Add

Flows (Q)

0
5
10

+
-

Plot...

Help
OK
Cancel

Figure 50: Roadside drainage downstream boundary condition input




Figure 51: Roadside drainage downstream normal depth rating curve

Hy-8 Culvert Properties Dialog Box

Crossing Properties

Name:

Parameter	Value	Units
DISCHARGE DATA	Optional--Model will determine va...	Optional Inf...
Discharge Method	Minimum, Design, and Maxim...	
Minimum Flow	0.000	cfs
Design Flow	0.000	cfs
Maximum Flow	0.000	cfs
TAILWATER DATA	Optional--Model will determine va...	Optional Inf...
Channel Type	Rectangular Channel	
Bottom Width	0.000	ft
Channel Slope	0.0000	ft/ft
Manning's n (channel)	0.000	
Channel Invert Elev...	0.000	ft
Rating Curve	View...	
ROADWAY DATA		
Roadway Profile Sh...	Constant Roadway Elevation	
First Roadway Station	25.950	ft
Crest Length	4.000	ft
Crest Elevation	358.000	ft
Roadway Surface	Paved	
Top Width	29.800	ft

Culvert Properties

Culvert 1

Parameter	Value	Units
CULVERT DATA		
Name	Culvert 1	
Shape	Circular	
Material	Corrugated Steel	
Diameter	4.000	ft
Embedment Depth	0.000	in
Manning's n	0.024	
Culvert Type	Straight	
Inlet Configuration	Mitered to Conform to Slope	
Inlet Depression?	No	
SITE DATA		
Site Data Input Option	Culvert Invert Data	
Inlet Station	0.000	ft
Inlet Elevation	351.555	ft
Outlet Station	74.190	ft
Outlet Elevation	349.449	ft
Number of Barrels	1	

Figure 52: HY-8 Culvert parameters for existing conditions simulation




Figure 53: Location of boundary conditions for the existing-conditions model




Figure 54: Location of boundary conditions for the natural-conditions model




Figure 55: Location of boundary conditions for the proposed-conditions model

4.1.5 Model Run Controls

The model controls used in the simulation for every flow event are shown in Figure 54. The result output frequency used was once per minute (0.016 hour) to begin with to troubleshoot the model and graduated to every 15 minutes (0.25 hour) once the model was stable.

Figure 56: Model controls

4.1.6 Model Assumptions and Limitations

The SRH-2D hydraulic model was developed to determine the minimum hydraulic structure opening, establish the proposed structure low chord elevation (and associated freeboard), and characterize hydraulic parameters used to design the crossing. The use of a constant inflow rate is an appropriate assumption to meet the model objectives. Using a constant inflow rate provides a conservative estimate of inundation extents and water surface elevation (WSEL) associated with a given peak flow, which is used to determine the structure size and low chord.

Using the approach described in this study, each scenario is run for a sufficient time to fill storage areas and for water surface elevations to stabilize until flow upstream equals flow downstream. This modeling method does not account for the attenuation of peak flows between the actual upstream and downstream hydrographs, in particular with a large amount of storage upstream of the existing undersized culvert. During an actual runoff event, it is unlikely that the area upstream of the culvert would fill up entirely. An unsteady simulation could be used to route a hydrograph through the model to estimate peak flow attenuation for existing and proposed conditions. During an unsteady simulation, the areas upstream of the existing culvert would act as storage and, as a result, the flow downstream of the crossing would likely be less than the current design peak flow event. Estimates of downstream increases to water surface elevation and flow based on the constant inflow model results may then underestimate the downstream flood impacts. An unsteady analysis is outside the current scope of this preliminary study but could be considered at a later stage of design. Therefore, the changes to the peak flow rate downstream of the project cannot be quantified with this approach.

The model results and recommendations in this report are based on the conditions of the project site and the associated watershed at the time of this study. Any modifications to the site, man-made or natural, could alter the analysis, findings, and recommendations contained herein and could invalidate the analysis, findings, and recommendations. Site conditions, completion of upstream or downstream projects, upstream or downstream land use changes, climate changes, vegetation changes, maintenance practice changes, or other factors may change over time. Additional analysis or updates may be required in the future as a result of these changes.

4.2 Existing-Conditions Model Results

Locations of the cross sections used for results reporting for existing-, natural-, and proposed-conditions models are shown in Figure 55. Three cross sections are located upstream and three are located downstream, with one in the center of the existing culvert and proposed structure. The longitudinal profile stationing can be seen in Figure 56.

Existing-conditions hydraulic results across the main channel are summarized for the upstream and downstream cross sections in Table 10. Under existing conditions, the culvert does not have capacity to convey the design flow. This causes backwater to fill the area upstream for the range of flows simulated (in Figure 57). Pressure flow conditions first occur at the 2-year flow event, when the headwater elevation exceeds 354.2 feet. The U.S. 101 roadway was not overtopped at the project culvert, but a smaller unnamed roadway aligned due west of U.S. 101 is overtopped at both the 100-year and 500-year events leading some flow to bypass the culvert.

Typical cross sections for downstream and upstream are found in Figure 58 and Figure 59, respectively. The downstream cross section shows a channel that, while confined, has an accessible floodplain. The upstream cross section shows an unconfined channel spreading flow into the floodplains at low flows. All cross sections were drawn perpendicular to flow. The 100-year velocity map for existing conditions can be seen in Figure 60. All cross sections are presented in Appendix C.

As a result of the backwater associated with the 48-inch-diameter culvert, the upstream depths are greater than the downstream reach. In addition, the cross section directly upstream of the structure (within the limits of backwater) has lower velocities and shear stresses than the other cross sections throughout the stream. Despite an average slope of approximately 3 percent compared to the downstream slope of 1 percent, the upstream reach cross sections have lower velocities than the downstream reach because existing log jams cause the flow to spread out across the floodplains outside of the main channel. Downstream velocities range from 3.0 ft/s to 5.8 ft/s during all flow events, while upstream velocities range from 1.0 ft/s (due to backwater conditions) to 4.1 ft/s during all flow events. Shear values remained consistent throughout the entire stream reach; they ranged from 0.6 to 1.6 pound per square foot (lb/SF) in the downstream cross sections, and from <0.1 to 1.8 lb/SF in the upstream cross sections. When looking at the entire model domain, the highest velocities occurred at the culvert outlet and at the cross section farthest downstream, where no backwater is present, and the flow is more confined than in the upstream cross sections. Figure 30 shows the 100-year velocity map with the cross-section locations depicted. Average velocities across the main channel, left overbank (LOB), and right overbank (ROB) of each cross section for the 100-year flow are shown in Table 11.




Figure 57: Locations of cross sections used for results reporting for existing-, natural-, and proposed-conditions models




Figure 58: Longitudinal profile stationing for existing, natural, and proposed conditions

Table 10: Hydraulic results for existing conditions within main channel

Hydraulic parameter	Cross section (STA)	2-year	100-year	500-year
Average water surface elevation (ft)	1+14.03	348.3	348.9	349.0
	1+55.82	348.8	349.8	349.8
	1+94.01	349.2	350.0	350.0
	2+65.97	353.4	354.4	354.8
	3+18.11	354.3	356.6	356.9
	4+15.61	356.9	357.2	357.3
	4+30.97	357.3	357.6	357.7
Maximum water depth (ft)	1+14.03	1.7	2.4	2.4
	1+55.82	1.7	2.7	2.8
	1+94.01	1.6	2.4	2.4
	2+65.97	1.8	2.8	3.2
	3+18.11	3.4	5.7	5.9
	4+15.61	2.2	2.6	2.7
	4+30.97	2.1	2.5	2.6
Average velocity magnitude (ft/s)	1+14.03	4.1	5.7	5.8
	1+55.82	3.0	3.8	3.8
	1+94.01	3.6	4.8	4.8
	2+65.97	6.8	9.5	10.4
	3+18.11	1.2	1.0	1.0
	4+15.61	3.3	4.1	4.1
	4+30.97	2.6	3.7	3.8
Average shear stress (lb/SF)	1+14.03	1.0	1.6	1.6
	1+55.82	0.6	0.6	0.6
	1+94.01	0.9	1.2	1.2
	2+65.97	0.8	1.4	1.6
	3+18.11	<0.1	<0.1	<0.1
	4+15.61	1.3	1.8	1.8
	4+30.97	0.9	1.3	1.4




Figure 59: Existing-conditions water surface profiles




Figure 60: Typical downstream existing-conditions channel cross section (STA 1+94)




Figure 61: Typical upstream existing-conditions channel cross section (STA 4+31)




Figure 62: Existing-conditions 100-year velocity map with cross-section locations

Table 11: Existing-conditions velocities including floodplains at select cross sections

Location	Q100 average velocities (ft/s)		
	LOB ^a	Main Ch.	ROB ^a
1+14.03	0.7	5.7	2.0
1+55.83	1.2	3.8	1.1
1+94.01	1.4	4.8	0.9
2+65.97	NA	9.5	NA
3+18.11	0.4	1.0	0.2
4+15.61	0.8	4.1	1.0
4+30.97	0.5	3.7	0.8

a. ROB/LOB locations were approximated at the tops of banks from inspecting the surface and 2-year top width.

4.3 Natural-Conditions Model Results

Natural-conditions hydraulic results for the main channel are summarized for the upstream and downstream cross sections as well as the cross section within the proposed crossing in Table 12. To create the natural conditions run, the road prism was removed beyond the wetted extents of the channel (approximately 50 feet of road were removed for this site), and the reference reach channel cross section was extended through the area otherwise occupied by the structure. Under natural conditions, the crossing does not backwater or overtop the smaller unnamed roadway heading west off of U.S. 101. However, flow is still spread across the floodplain in the upstream, unconfined channel because of accessible floodplains and log jams that cause the channel to spread. The WSELs for the range of flows simulated are shown in Figure 61. The 2080 predicted 100-year flow WSEL is nearly equal to the 500-year flow.

Upstream depths are similar to those in the downstream reach. The upstream depths range from 1.5 to 2.6 feet in upstream cross sections, while downstream depths range from 1.3 to 3.0 feet. Depths are 1.4 to 2.2 feet through the removed road embankment. Velocities range from 2.9 to 4.9 ft/s in the upstream reach, and from 3.1 to 6.1 ft/s in the downstream reach. The velocity is 3.6 to 4.8 ft/s through the space the culvert previously occupied. The similarities in velocity are easily explained by looking at the cross-section shapes and slopes; while the slope is approximately 2.2 percent upstream, flow also spreads farther out across floodplains. Downstream, the slope is roughly 1.5 percent, but flow is confined mostly to the channel and occasional accessible floodplains. Shear values range from 0.9 to 2.0 lb/SF in the upstream cross sections, and 0.5 to 2.4 lb/SF in the downstream cross sections. Shear in the former culvert cross section ranged from 1.3 to 1.9 lb/SF. When looking at the entire model domain, the largest velocities occur upstream where flow enters pools around log jams. Average velocities across the main channel, LOB, and ROB of each cross section for the 100-year flow are in Table 13. A velocity map showing the 100-year flow is in Figure 64.

Typical cross sections for downstream and upstream are found in Figure 62 and Figure 63, respectively. The downstream cross section shows a channel that, while confined, has an accessible floodplain. The upstream cross section shows an unconfined channel spreading flow into the floodplains at low flows. All cross sections are provided in Appendix C.

Table 12: Hydraulic results for natural conditions within main channel

Hydraulic parameter	Cross-section (STA)	2-year	100-year	2080 predicted 100-year	500-year
Average water surface elevation (ft)	1+14.03	348.3	349.0	349.2	349.1
	1+55.82	348.8	349.8	350.1	350.0
	1+94.01	349.8	350.4	350.6	350.6
	2+65.97 ^a	351.3	351.9	352.1	352.1
	3+18.11	352.4	353.0	353.2	353.2
	4+15.61	356.9	357.3	357.3	357.3
	4+30.97	357.2	357.6	357.7	357.7
Maximum water depth (ft)	1+14.03	1.7	2.4	2.6	2.6
	1+55.82	1.7	2.7	3.0	3.0
	1+94.01	1.3	1.9	2.1	2.1
	2+65.97 ^a	1.4	2.0	2.2	2.1
	3+18.11	1.5	2.1	2.2	2.2
	4+15.61	2.3	2.6	2.6	2.6
	4+30.97	2.1	2.4	2.5	2.5
Average velocity magnitude (ft/s)	1+14.03	4.2	5.7	6.1	6.1
	1+55.82	3.1	3.9	4.1	4.1
	1+94.01	4.1	5.2	5.3	5.3
	2+65.97 ^a	3.6	4.6	4.8	4.8
	3+18.11	3.6	4.6	4.9	4.9
	4+15.61	3.3	4.1	4.3	4.2
	4+30.97	2.9	3.9	4.1	4.1
Average shear stress (lb/SF)	1+14.03	1.0	1.6	1.8	1.8
	1+55.82	0.5	0.7	0.7	0.7
	1+94.01	1.7	2.4	2.4	2.4
	2+65.97 ^a	1.3	1.8	1.9	1.9
	3+18.11	1.3	1.8	2.0	2.0
	4+15.61	1.3	1.8	1.9	1.9
	4+30.97	0.9	1.4	1.5	1.5

a. Cross section located at removed roadway embankment.




Figure 63: Natural-conditions water surface profiles




Figure 64: Typical downstream natural-conditions channel cross section (STA 1+94)




Figure 65: Cross section (STA 2+65) through removed structure for natural conditions




Figure 66: Typical upstream natural-conditions channel cross section (STA 4+31)




Figure 67: Natural-conditions 100-year velocity map with cross-section locations

Table 13: Natural-conditions velocities including floodplains at select cross sections

Location	Q100 Average Velocities (ft/s)		
	LOB ^a	Main Ch.	ROB ^a
1+14.03	0.7	5.7	1.9
1+55.83	1.2	3.9	1.0
1+94.01	1.4	5.2	1.2
2+65.97 ^b	1.7	4.6	1.8
3+18.11	1.2	4.6	0.8
4+15.61	0.8	4.1	1.0
4+30.97	0.5	3.9	0.8

a. ROB/LOB locations were approximated at the tops of banks from inspecting the surface and 2-year top width.

b. Cross section located at removed roadway embankment.

4.4 Channel Design

Channel design for proposed conditions includes the floodplain utilization ratio (FUR), channel planform, shape, alignment, and gradient.

4.4.1 Floodplain Utilization Ratio

The FUR is defined as the flood-prone width (FPW) divided by the BFW. FPW is the water surface width at twice the bankfull depth, or the width at the 50-year to 100-year flood. A ratio under 3.0 is considered a confined channel and above 3.0 is considered an unconfined channel. When removing the culvert backwater influence by performing a model run simulation with a 20-foot-diameter culvert, the FPW upstream of the culvert inlet was measured three times, and the FPW downstream was measured twice. These values are identified below in Table 14, and the locations where they were measured are shown in Figure 65.

Using a BFW of 10.3 feet, these FPWs result in an average FUR of 7.9, denoting this channel as unconfined.

Table 14: Flood-prone widths and floodplain utilization ratio results

Parameter	Measurements (ft)					
	Downstream		Upstream			Average
	1	2	3	4	5	-
FPW (measured from 100-year top width of model)	44	21	104	126	113	81.6
Associated FUR	4.3	2.0	10.1	12.2	11.0	7.9
Average FUR (upstream and downstream)	3.2		11.1			




Figure 68: Locations of FPW measurements

4.4.2 Channel Planform and Shape

The WCDG requires that the channel planform and shape mimic conditions within a reference reach. The proposed channel shape includes 10 horizontal (H):1 vertical (V) slopes between the centerline and bank toe and 2H:1V bank slopes to create a channel similar to the reference channel shape. Floodplain slopes at 16H:1V simulate the reference floodplains and channel benches, thereby connecting the proposed grading to the existing surface. This is shown in Figure 66.

The identified reference reach was chosen downstream of the culvert because the upstream reach is populated with log jams and the stream channel does not display natural conditions, as explained earlier in this PHD Report. The design channel shape is based on the reference reach shape. In Figure 67, the reference channel shape is shown as a brown dashed line and is located at STA 1+88.98, which is inside the reference reach identified in Section 2.8.1. The design channel shape is shown in solid green. The proposed grading was evaluated in SMS. The natural-conditions model was used to view the 2-year flow depth to confirm that the flow was approximately at the top of banks of the proposed grading. Also, the top widths for all flow events at the reference reach were compared to the top widths at the proposed structure. Channel benches are activated at flows as low as the 2-year event upstream and at several

locations downstream as well. The top widths of the reference reach and proposed structure location were similar, demonstrating that the proposed grading accurately reflects the channel shape of the reference reach.

This channel does not show the integration of LWM into the bed or within the channel banks, which will be a critical feature to support reduction of the downstream channel gradient and increase to hydraulic roughness to maintain a lower gradient reach with sufficiently low velocities to reduce grain size and support pool-riffle morphology. Those details will be determined in the FHD.

The channel design cross-section is expected to respond over time to mimic the existing shape, namely the lowering of the thalweg. The channel is expected to maintain its overall general shape but will adjust to form channel features such as low-flow meanders and pools from large woody material (LWM).

A low-flow channel will be added in during the Final Hydraulic Design stage of the project that connects habitat features together so that the project is not a low-flow barrier. The low-flow channel will be placed as directed by the engineer in the field.




Figure 69: Design cross section




Figure 70: Proposed versus existing cross section

4.4.3 Channel Alignment

The proposed project alignment follows the existing alignment. The project will include channel grading approximately 175 feet downstream of the channel outlet to roughly 25 feet upstream of the channel inlet. The channel alignment was constrained on the upstream side because of a large log jam surveyed. Field observations indicate that the existing log jam, composed of wood recruited from historical logging activities, obstructs flow during flood events, redirects water to accessible floodplain surfaces, and retains fine sediments in the upstream reach. The proposed grading limit ends prior to this log jam so that it is not disturbed.

Lengthening the radius of curvature in the channel bend downstream of the culvert was considered, but hydraulic model results do not indicate a high risk of local erosion on the right bank compared to existing conditions. At the 2-year event, modeled velocity is relatively uniform in the downstream reach under proposed conditions. Therefore, realigning the downstream reach would not provide a significant benefit to habitat and hydraulic complexity.

4.4.4 Channel Gradient

The WCDG recommends that the proposed structure bed gradient not be more than 25 percent steeper than the existing stream gradient upstream of the crossing (WCDG Equation 3.1). The proposed channel gradient is 2.0 percent. The average upstream slope over approximately 2,000 feet of LiDAR data is 2.2 percent. The corresponding slope ratio is 0.9, which is within the recommended WCDG limits.

As discussed in Section 2.8, due to the known disparity in slope between the reference reach and the design reach, the slope ratio comparison was based on the slope of the upstream reach, 2.2%, resulting in a slope ratio of 0.90 (Figure 39 above). The reference reach slope (1.5 percent) would be too flat for the grading to connect upstream. The Draft PHD proposed a slope of 2.6 percent to minimize grading outside of the existing structure footprint, but this was too steep for the reach and did not meet stream simulation criteria. We propose to grade the structure at a 2.0 percent slope, which is an intermediate value between the surveyed upstream and downstream slopes. This involves extending the grading approximately 175 feet downstream of the crossing and provides an opportunity to improve habitat conditions in the degraded downstream reach by re-meandering the channel and placing 6 to 8 inches of fill in incised areas to improve floodplain connectivity. Channel response is possible at the transition between the proposed design slope and the existing upstream gradient, which is described in more detail in Section 8.2.

4.5 Design Methodology

The proposed fish passage design was developed using the 2013 *Water Crossing Design Guidelines* (Barnard et al. 2013) and the WSDOT *Hydraulics Manual* (WSDOT 2019). Using the guidance in these two documents, the unconfined bridge design method was determined to be the most appropriate at this crossing because the FUR was calculated to be greater than 3.0.

Two requirements for the stream simulation method were met: the BFW was less than 15 feet, and the proposed channel gradient meets the slope ratio. However, the FUR was calculated to be more than 3.0, which means the channel is unconfined and the unconfined bridge approach must be used to allow for flow in the floodplains.

4.6 Future Conditions: Proposed 15-Foot Minimum Hydraulic Opening

The hydraulic opening is defined as the width perpendicular to the creek beneath the proposed structure that is necessary to convey the design flow and allow for natural geomorphic processes. The hydraulic opening assumes vertical walls at the edge of the minimum hydraulic opening width unless otherwise specified.

The starting point for the design of all WSDOT structures is Equation 3.2 of the WCDG, rounded up to the nearest whole foot. For this crossing, a minimum hydraulic opening of 15 feet was determined to be the minimum starting point based on a BFW of 10.3 feet determined from field measurements during the second site visit on June 25, 2021 and confirmed with WSDOT topographic survey, modeled 2-year flow width, and WDFW climate-predicted BFW estimates described in Section 2.8.2.

Proposed-conditions hydraulic results are summarized for the upstream and downstream cross sections as well as the cross section within the proposed crossing in Table 15. A cross section showing WSEL in the proposed structure is shown in Figure 69. The larger proposed structure reduced water surface elevations upstream and does not cause backwater (Figure 68). The 2080 projected 100-year flow WSEL is nearly equal to the 500-year flow. The 100-year water surface elevation at the upstream cross section (STA 3+18) decreased by 3.5 feet from existing conditions. Also, there is no overtopping of U.S. 101 or of the unnamed roadway heading west off of U.S. 101 under proposed conditions and all flow is conveyed through the proposed opening.

Upstream channel velocities vary from 2.9 to 4.9 ft/s, and the downstream proposed-conditions velocities vary from 3.1 to 6.1 ft/s. Velocities upstream and downstream have both increased slightly under proposed conditions due to the increase in conveyance from existing conditions.

In upstream cross sections, shear stress increases slightly from existing conditions because of the removal of backwater at the culvert inlet, where computed values vary from 0.9 to 1.9 lb/SF. Computed shear stresses in downstream cross sections remain close to shear stresses seen in existing conditions. Values vary from 0.5 to 2.4 lb/SF. Average velocities across the main channel, LOB, and ROB of each cross section for the 100-year flow are summarized in Table 16. A velocity map showing the 100-year flow is in Figure 70, and a second velocity map showing the 2080 predicted 100-year flow is in Figure 71.

The proposed crossing structure decreases the change between the upstream and downstream shear stresses, depth, and velocities, thereby reducing the discontinuities in hydraulic conditions within the project reach (Figure 70).

Table 15: Hydraulic results for proposed conditions within main channel

Hydraulic parameter	Cross section (STA)	2-year	100-year	2080 predicted 100-year	500-year
Average water surface elevation (ft)	1+14.03	348.3	349.0	349.2	349.1
	1+55.82	348.8	349.8	350.1	350.0
	1+94.01	349.8	350.4	350.6	350.6
	2+65.97 ^a	351.4	352.1	352.3	352.2
	3+18.11	352.5	353.2	353.4	353.4
	4+15.61	356.9	357.3	357.3	357.3
	4+30.97	357.2	357.6	357.7	357.7
Maximum water depth (ft)	1+14.03	1.7	2.4	2.6	2.6
	1+55.82	1.7	2.7	3.0	3.0
	1+94.01	1.3	1.9	2.1	2.1
	2+65.97 ^a	1.5	2.1	2.4	2.3
	3+18.11	1.5	2.2	2.5	2.4
	4+15.61	2.3	2.6	2.6	2.6
	4+30.97	2.1	2.4	2.5	2.5
Average velocity magnitude (ft/s)	1+14.03	4.2	5.7	6.1	6.1
	1+55.82	3.1	3.9	4.1	4.1
	1+94.01	4.0	5.2	5.4	5.3
	2+65.97 ^a	3.5	4.8	5.1	5.1
	3+18.11	3.4	4.3	4.5	4.5
	4+15.61	3.3	4.1	4.2	4.2
	4+30.97	2.9	3.9	4.1	4.1
Average shear stress (lb/SF)	1+14.03	1.0	1.6	1.8	1.7
	1+55.82	0.5	0.7	0.7	0.7
	1+94.01	1.7	2.4	2.4	2.4
	2+65.97 ^a	1.2	1.9	2.1	2.1
	3+18.11	1.1	1.6	1.6	1.6
	4+15.61	1.3	1.8	1.9	1.9
	4+30.97	0.9	1.4	1.5	1.5

a. Cross section located within proposed structure.




Figure 71: Proposed-conditions water surface profiles




Figure 72: Section through proposed structure (STA 2+65)




Figure 73: Proposed-conditions 100-year velocity map. Flow direction is from bottom to top of figure.

Table 16: Proposed-conditions velocities including floodplains at select cross sections

Location	Q100 average velocities (ft/s)		
	LOB ^a	Main ch.	ROB ^a
1+14.03	0.7	5.7	1.9
1+55.83	1.2	3.9	1.0
1+94.01	1.5	5.2	1.2
2+65.97 ^b	2.9	4.8	3.0
3+18.11	1.5	4.3	0.9
4+15.61	0.8	4.1	1.0
4+30.97	0.5	3.9	0.8

- a. ROB/LOB locations were approximated at the tops of banks from inspecting the surface and 2-year top width.
b. Cross section located at proposed structure.




Figure 74: Proposed-conditions 2080 predicted 100-year velocity map. Flow direction is from bottom to top of figure.

4.7 Water Crossing Design

Water crossing design for Harlow Creek includes structure type, minimum hydraulic opening width and length, and freeboard requirements.

4.7.1 Structure Type

This PHD Report does not recommend a specific structure type. The layout and structure type will be determined at the FHD phase.

4.7.2 Minimum Hydraulic Opening Width and Length

The WCDG recommends sizing the span of the proposed structure based on the agreed-upon BFW, with the span being $1.2 \times \text{BFW} + 2$ feet (WCDG Equation 3.2). Using this equation, along with the modeled BFW of 10.3 feet discussed in Section 2.8.2, results in a structure span of 14.4 feet. Rounding up to the nearest whole foot results in a recommended structure span of 15 feet.

Observations from the site visit indicate that large log jams, formed by wood from historic logging activities, influence channel form by spreading flood flows across nearby floodplain surfaces. There is not a significant risk of lateral migration within the upstream reach of the culvert due to the abundance of large wood accumulations that span the channel corridor and the relatively broad surface that is activated during flood events, coupled with the significant root mass from conifers growing on both banks. Therefore, lateral migration was not accounted for in width determination. This wood also appears to have been stable for long enough for individual pieces to begin to degrade, and debris load is not expected to be a criterion influencing width determination. The BFW value used to determine structure size accounts for the inset floodplain surfaces expected to be engaged under channel-forming flows. Based on the factors described above, a minimum hydraulic opening of 15 feet was determined to be sufficient to accommodate natural processes under the current flow and sediment transport regimes. The proposed design, with a 2 percent slope, meets velocity ratio criteria.

A comparison of computed velocities under proposed- and natural-conditions with the current 100-year and predicted 2080 increase in 100-year flows is shown in Table 17.

Table 17: Velocity comparison for proposed 15-foot-wide structure opening

Location	Proposed conditions			Natural conditions		
	100-Year velocity (ft/s)	2080 predicted 100-Year velocity (ft/s)	Difference (ft/s)	100-Year velocity (ft/s)	2080 predicted 100-Year velocity (ft/s)	Difference (ft/s)
Upstream of structure (XS 3+18.11)	4.3	4.5	0.2	4.6	4.9	0.3
Through structure (XS 2+65.97)	4.8	5.1	0.3	4.6	4.8	0.2
Downstream of structure (XS 1+55.83)	3.9	4.1	0.2	3.9	4.1	0.2
Velocity ratio	1.1	1.1		1.0	1.0	

Note: Velocity ratio calculated as $V_{\text{structure}}/V_{\text{upstream}}$.

Velocities in the upstream reach are dampened by the presence of in-channel wood, including logjams, which add flow resistance and encourage multiple flow paths through the main channel and floodplain. This area and the proposed channel, which will be designed to mimic natural roughness, were assigned a Manning's roughness coefficient of 0.06 in the proposed conditions model, while the simplified channel downstream of the culvert was assigned a Manning's roughness coefficient of 0.045.

No size increase was determined to be necessary to accommodate climate resilience. A minimum hydraulic opening of 15 feet is recommended, and there is no length recommendation for the proposed structure.

4.7.3 Freeboard

The WCDG recommends that structure designs prevent excessive backwater rise and increased main channel velocities during floods that might lead to scour of the streambed and coarsening of the stream substrate, allow the free passage of debris expected to be encountered, and generally suggests a minimum 2 feet of freeboard for streams of this size above the 100-year water surface elevation. WSDOT is incorporating climate resilience in freeboard, where practicable, and has evaluated freeboard at both the 100-year water surface elevation and the projected 2080 100-year water surface elevation.

While the LWM design is conceptual in nature, an additional model run was performed to increase roughness in the channel to reflect anticipated future installation of LWM. Because of the uncertainty of the LWM design, roughness was increased by 0.03 for an additional factor of safety with respect to freeboard. This value represents increased obstructions occupying approximately 15 to 50 percent of cross section area (Yochum 2017).

The minimum required freeboard at this location based on BFW was 2 feet at the 100-year flow event. The water depth at the 100-year flow event at the deepest point within the structure is 2.1 feet. The 2080 projected 100-year water depth at this point is 2.4 feet. A minimum structure height of 4.4 feet

above the thalweg is required to meet the minimum freeboard requirements for the 2080 projected 100-year. If it is practicable to do so, a minimum of 6 feet between the channel thalweg elevation and inside top of structure is recommended for maintenance and monitoring purposes. The PHD drawings currently assume that 6 feet of clearance is practicable. If determined not to be practicable during future phases of design, the clearance must be a minimum of 4.4 feet.

Long-term degradation, aggradation, and debris risk were also evaluated at this location. Because the proposed culvert is slightly steeper than the downstream reach, the 1.5 percent slope of the downstream reach was carried through the structure and evaluated at the upstream inlet. If the shallower slope of the reference reach was used, the structure inlet would be approximately 1 to 2 feet lower in elevation. Countersinking of the structure will take this into account during the Final Hydraulic Design (FHD) analysis and will include potential future degradation and long-term scour. More information on the risk for long-term degradation and aggradation can be found in Section 8.

4.7.3.1 Past Maintenance Records

As discussed previously in Section 2.4, no maintenance records are available for this crossing.

4.7.3.2 Wood and Sediment Supply

Harlow Creek flows through a heavily wooded basin with a high potential for recruitment, as evidenced within the survey limits. Logging activities have occurred occasionally throughout the basin (Section 2.1), which has likely reduced the supply of large stable wood and may increase the sediment supply. It is likely that basin development will remain largely unchanged in the future, with the exception of periodic logging. The large wood transport in this reach is limited by the capacity to transport mature trees and by the presence of channel-spanning logjams upstream of the crossing. There is a relatively high density of existing large wood within the channel within the project reach due to historic logging.

Deposition occurred upstream of and around the log jams, indicating a healthy sediment supply in the reach. The proposed increase in structure width will increase flood conveyance and capacity for bedload transport to the downstream reach under channel forming flows, which will benefit habitat conditions through the project reach.

4.7.3.3 Flooding

Though FEMA has not conducted a Special Flood Hazard Area analysis at this site (Section 2.3), the roadway of U.S. 101 does not overtop under existing conditions for any modeled flow event. Backwater is present under all flow conditions, propagating approximately 65 feet upstream. The unnamed roadway heading west off of U.S. 101, however, overtops at both the 100-year and 500-year flow events.

The proposed structure will reduce upstream flooding extents; according to the model and flow results outlined in Section 4.6, the unnamed roadway will no longer overtop at any of the modeled flow events. As the unconfined channel converges at the inlet of the structure, a pool forms, but no backwater is present in the stream reach under the proposed conditions.

4.7.3.4 Future Corridor Plans

There are currently no long-term plans to improve U.S. 101 through this corridor.

4.7.3.5 Impacts

It is not anticipated that the road level will be raised to accommodate the proposed minimum hydraulic opening. A final decision will be made at a later design phase.

4.7.3.6 Impacts to Fish Life and Habitat

In discussion with WDFW and the Tribe, it is expected that the proposed minimum hydraulic opening of 15 feet will not result in substantial detrimental impacts to fish life and habitat.

DRAFT

5 Streambed Design

During the site visit, streambed sediment size was observed at the site and used to create a design sediment size for the proposed grading.

5.1 Bed Material

The proposed bed material gradation was created using standard WSDOT specification material. The proposed mix will consist of 30 percent streambed sediment, 40 percent 6-inch cobbles, and 30 percent 10-inch cobble. A comparison of the reference reach pebble count and proposed streambed material size distribution is provided in Table 19. When comparing the observed and proposed sediment sizes, it is relevant to remember that the reference reach has slightly lower slope (1.5 percent) than the design reach (2.0 percent). Because there is a risk of near-term washout of the sediment and entrainment of fines within the structure if the observed gradation is used, we recommend a slightly coarser proposed mix for this location (D_{50} of 2.0 inches as opposed to an observed D_{50} of 1.3 inches). The goal of the design team was that the D_{50} should be stable at a 2-year event to prevent excessive loss of material from the culvert during the first few storm seasons, while the material develops a natural armor layer, and the system has an opportunity to respond to the geomorphic effects of the design LWM.

Table 18: Comparison of observed and proposed streambed materials

Sediment Size	Observed Diameter (in)	Proposed Diameter (in)	Meander Bar Diameter (in)
D₁₆	0.4	0.6	0.6
D₅₀	1.3	2.0	3.3
D₈₄	2.9	5.4	13.2
D₉₅	4.0	8.3	16.5
D₁₀₀	10.1	10.0	18.0

The Modified Critical Shear Stress Approach (as described in Appendix E of the United States Forest Service [USFS] Guidelines) was used to analyze mobility for the proposed streambed material at the project site (USFS 2008). The sediment mobility analysis indicates that for the observed gradation, only material sizes larger than the D_{84} would be stable at the 2-year event and all material sizes would mobilize at the 100-year flow. The proposed gradation is designed such that the larger material (D_{50} and larger) will provide a degree of stability for smaller material, while still being deformable at the 2-year event. The D_{50} was selected as the threshold for stability at the 2-year event to prevent too large a fraction of the material in the culvert from mobilizing at a relatively frequent interval and to reduce the risk of localized streambed degradation and bed coarsening. In addition, the sediment input from upstream is expected to be low in the foreseeable future, as evidenced by the number of full-spanning logging debris jams and the predominantly fine materials evident within the upstream channel. Meander bars are included to control channel shape and initiate stream structure. The bars are composed of well-graded streambed material that is between 1 and 2 times the D_{100} of the existing streambed mix. The meander bar mix is composed of 30 percent streambed sediment, 50 percent 10-inch streambed cobble, and 20 percent 1-man streambed boulders. The meander bar mix is stable at the

D₅₀ and above for the 2-year event and at the D₈₄ and above for the 100-year flow event. See Appendix D for streambed sizing and sediment mobility calculations.

5.2 Channel Complexity

To encourage a complex channel that is more habitable for fish, a design including both LWM and non-LWM structures was developed.

5.2.1 Design Concept

The LWM concept is first based on an approach of incorporating wood within the entire channel cross-section, including within the channel bed, within the active low-flow channel and as overhead cover above the channel invert. Secondly the approach is to use a whole tree when harvesting a rootwad log. This “whole tree” design approach is based first on identifying the diameter and length of the rootwad log needed, then incorporating the remaining pieces of the tree that can be created from the harvest of that tree. During final design, it will be illustrated how to incorporate the slash and branches from the harvest of the tree, such that the whole tree is used in the project site, rather than leaving significant waste / slash piles at the harvest site. The layout below is the conceptual orientation of a series of structures intended to initiate local channel evolution of complex instream habitat, including lateral scour to increase thalweg sinuosity and decrease overall channel slope (Figure 75). This complex matrix of wood will provide very high hydraulic roughness, reducing stream power and generating low-velocity refuge areas in the channel during storm flows.

The 75th percentile of key piece density in accordance with Fox and Bolton (2007) and Chapter 10 of the *Hydraulics Manual* recommend 3.4 key pieces and 39.48 cubic yards of volume per 100 feet of channel. This percentile of wood placement is suggested. A conceptual LWM layout based on the assumption of a buried structure has been developed for this project area and is provided in Figure 72. The conceptual layout proposes 22 key pieces in a 145.5-foot-long project reach (including the structure length), yielding 15.2 key pieces per 100 feet of linear channel length. This satisfies and exceeds the Fox and Bolton (2007) 75th percentile criterion with a total key piece loading of 440 percent of target. The conceptual layout exceeds total LWM volume target by approximately 7 percent.

Wood structures placed in the stream will serve as habitat features for fish, add hydraulic complexity, and increase the stream’s ability to sort and retain gravels useful for fish habitat. The complex wood matrix will provide beneficial geomorphic and habitat function; providing multiple flow paths through and around the structure where minor channel bed and bank deformation is encouraged, while dissipating flow energy at higher flows. Arranging logs in typical clusters that alternate along streambanks provides an intentional meandering of the main channel thalweg, while increasing the efficiency and repeatability of wood placement during construction.

A key component of the conceptual design is that wood pieces will be oriented at varying degrees of pitch angle (horizontal) to provide flow-through paths above and below the logs, and to avoid formation of a “weir” effect in the long term. Additionally, wood pieces will be oriented at varying angles relative to streamflow (longitudinally) so there is adequate space for the channel to form pools and buildup of sediment deposits. Wood will be installed both within the low-flow channel and within the floodplain area to increase its engagement with flow at all conditions to provide refuge areas during storm flows.

The majority of wood will be placed downstream of the crossing as significant wood already exists upstream of the culvert inlet. Within the crossing structure, coarse bands will span perpendicular to flow and installed in a concave shape to retain gravels, create channel complexity and encourage a low flow notch to develop through natural processes. Wood stability will be assessed at the FHD level; at this time, anchoring is not anticipated. During the FHD, an analysis will be performed to determine at which flows the mobile wood in the stream becomes mobile.

Risk of fish stranding during summer flow conditions is minimal because a continuous meandering thalweg is anticipated to develop, winding between scour pools generated by the hydraulics of storm flows interacting with the rootwads. No special design considerations should be made.




Figure 75: Conceptual layout of habitat complexity

6 Floodplain Changes

No FEMA flood hazard analysis was available for this location (Section 2.3). The pre-project and expected post-project conditions were evaluated to determine whether there would be a change in water surface elevation and floodplain storage.

6.1 Floodplain Storage

Floodplain storage is anticipated to be significantly impacted by the proposed structure. The installation of a larger hydraulic opening will reduce the amount of backwater and associated peak flow attenuation that was being provided by the smaller, existing culvert. A comparison of pre- and post-project peak flow events was not quantified as the models were run with a constant flow rate specified at the upstream boundary of the model, therefore only the peak discharge of flood events was evaluated. An unnamed road heading west off of U.S. 101 will no longer be overtopped after installation of the proposed structure and, as a result, secondary flow from Harlow Creek will no longer enter road drainage on the west side of U.S. 101. All flow will remain with the channel.

6.2 Water Surface Elevations

Installation of the proposed structure would eliminate the backwater impacts just upstream of the existing culvert, resulting in a reduction in water surface elevation upstream. The water surface elevation is reduced by as much as 3.6 feet at the inlet of the existing culvert at the 100-year event as shown in Figure 73 and Figure 74. Figure 74 also depicts the extent of backwater and the overtopping of the unnamed roadway heading west off of U.S. 101 that is eliminated.

Immediately downstream of the culvert, channel regrading for proposed conditions causes a rise by as much as 1.9 feet in water surface near STA 2+28. The local water surface rise is a result of the fill in the scour hole downstream of the existing culvert outlet. Past the outlet, the water surface change varies between no change and less than a 0.1-foot rise from the existing to proposed conditions.




Figure 76: Existing and proposed 100-year water surface profile comparison




Figure 77: 100-year water surface elevation change. Flow direction is from bottom to top of figure.

In Figure 74, positive values indicate an increase in water surface elevation from existing to proposed conditions. Black represents new water surface extents and purple represents water surface extents that have been removed.

7 Climate Resilience

WSDOT recognizes climate resilience as a component of the integrity of its structures and approaches the design of bridges and buried structures through a risk-based assessment beyond the design criteria. For bridges and buried structures, the largest risk to the structures will come from increases in flow and/or sea level rise. The goal of fish passage projects is to maintain natural channel processes through the life of the structure and maintain passability for all expected life stages and species in a system.

7.1 Climate Resilience Tools

WSDOT also evaluates crossings using the mean percent change in 100-year flood flows from the WDFW Future Projections for Climate-Adapted Culvert Design program. All sites consider the 2080 mean percent increase throughout the design of the structure. Appendix I contains the information received from WDFW for this site.

7.2 Hydrology

For each design WSDOT uses the best available science for assessing site hydrology. The predicted flows are analyzed in the hydraulic model and compared to field and survey indicators, maintenance history, and any other available information. Hydraulic engineering judgment is used to compare model results to system characteristics; if there is significant variation, then the hydrology is reevaluated to determine whether adjustments need to be made, including adding standard error to the regression equation, basin changes in size or use, etc.

In addition to using the best available science for current site hydrology, WSDOT is evaluating the structure at the 2080 predicted 100-year flow event to check for climate resilience. The design flow for the crossing is 91.1 cfs at the 100-year storm event. The projected increase for the 2080 flow rate is 24.2 percent, yielding a projected 2080 flow rate of 113.2 cfs.

7.3 Climate Resilience Summary

A minimum hydraulic opening of 15 feet and a minimum low chord elevation of 6 feet above the thalweg allows for the channel to behave similarly through the structure as it does in the adjacent reaches under the projected 2080 100-year flow event. This will help to ensure that the structure is resilient to climate change and the system is allowed to function naturally, including the passage of sediment, debris, and water in the future while accommodating WSDOT Maintenance clearance.

8 Scour Analysis

Total scour will be computed during later phases of the project using the 100-year, 500-year, and projected 2080 100-year flow events. The structure will be designed to account for the potential scour at the projected 2080 100-year flow events. For this phase of the project, the risk for lateral migration and potential for degradation are evaluated on a conceptual level. This information is considered preliminary and is not to be taken as a final recommendation in either case.

8.1 Lateral Migration

Channel migration was assessed by using historical imagery and modeling results. The historical aerial imagery gives little information on channel migration near the project site because the channel is in a forested area, making it difficult to decipher where the channel is in each aerial.

Observations from the site visit showed that upstream, flow is pushed into the floodplains as a result of large log jams formed from historic logging activities. Lateral migration could potentially occur in the upstream reach; however, all flow rejoins the channel at a scour pool upstream of the culvert inlet. As a result, lateral migration is not expected to occur within or around the culvert because the flow path in the channel directly upstream of the culvert is well defined. Lateral migration was not accounted for in width determination.

8.2 Long-term Aggradation/Degradation of the Riverbed

There is a risk of degradation based on the proposed channel grading. The slope of the culvert, 2.0 percent, is steeper compared to the slope of the downstream reach, 1.5 percent. As a result, extending the downstream slope of 1.5 percent through the culvert reveals that there is a potential for 1 to 3 feet of long-term degradation.

Summary

Table 20 presents a summary of this PHD Report results.

Table 19: Report summary

Stream crossing category	Elements	Values	Report location
Habitat gain	Total length	3,600'	2.4 Site Description
Bankfull width	Average BFW	10.3'	2.8.2 Channel Geometry
	Reference reach found?	Y	2.8.1 Reference Reach Selection
Channel slope/gradient	Existing crossing	2.8%	2.8.4 Vertical Channel Stability
	Reference reach	1.5%	2.8.2 Channel Geometry
	Proposed	2.0%	4.4.2 Channel Planform and Shape
Countersink	Proposed	FHD	4.7.3 Freeboard
	Added for climate resilience	FHD	4.7.3 Freeboard
Scour	Analysis	See link	8 Scour Analysis
	Streambank protection/stabilization	See link	8 Scour Analysis
Channel geometry	Existing	See link	2.8.2 Channel Geometry
	Proposed	See link	4.4.2 Channel Planform and Shape
Floodplain continuity	FEMA mapped floodplain	N	6 Floodplain Changes
	Lateral migration	N	2.8.5 Channel Migration
	Floodplain changes?	Y	6 Floodplain Changes
Freeboard	Proposed	2'	4.7.3 Freeboard
	Added for climate resilience	Y	4.7.3 Freeboard
	Additional recommended	1.6'	4.7.3 Freeboard
Maintenance clearance	Proposed	6'	4.7.3 Freeboard
Substrate	Existing	TBD	2.8.3 Sediment
	Proposed	TBD	5.1 Bed Material
Hydraulic opening	Proposed	15'	4.7.2 Minimum Hydraulic Opening Width and Length
	Added for climate resilience	N	4.7.2 Minimum Hydraulic Opening Width and Length
Channel complexity	LWM	Y	5.2 Channel Complexity
	Meander bars	Y	5.2 Channel Complexity
	Boulder clusters	N	5.2 Channel Complexity
	Mobile wood	Y	5.2 Channel Complexity
Crossing length	Existing	74'	2.7.2 Existing Conditions
	Proposed	See link	4.7.2 Minimum Hydraulic Opening Width and Length
Floodplain utilization ratio	Flood-prone width	81.6	4.4.1 Existing-Conditions Model Results
	Average FUR upstream and downstream	11.1/3.1	4.4.1 Existing-Conditions Model Results

Hydrology/design flows	Existing	See link	3 Hydrology and Peak Flow Estimates
	Climate resilience	See link	3 Hydrology and Peak Flow Estimates
Channel morphology	Existing	See link	2.8.2 Channel Geometry
	Proposed	See link	5.2 Channel Complexity
Channel degradation	Potential?	Y	8.2 Long-term Aggradation/Degradation of the Riverbed
	Allowed?	Y	8.2 Long-term Aggradation/Degradation of the Riverbed
Structure type	Recommendation	N	4.7.1 Structure Type
	Type	NA	4.7.1 Structure Type

DRAFT

References

Aquaveo. 2018. SMS Version 13.0.12.

Barnard, R.J., J. Johnson, P. Brooks, K.M. Bates, B. Heiner, J.P. Klavas, D.C. Ponder, P.D. Smith, and P.D. Powers. 2013. *Water Crossing Design Guidelines*. Washington State Department of Fish and Wildlife. Olympia, Washington.

Chow, V.T. 1959. *Open Channel Hydraulics*, McGraw-Hill Book Company, New York.

Fox, Martin and Bolton, Susan. 2007. A Regional and Geomorphic Reference for Quantities and Volumes of Instream Wood in Unmanaged Forests Basins of Washington Stat. *North American Journal of Fisheries Management*. Vol 27, Issue 1. Pg. 342–359.

Gerstel, W.J.; Lingley, W.S., Jr. 2000. Geologic map of the Forks 1:100,000 quadrangle, Washington: Washington Division of Geology and Earth Resources Open File Report 2000-4, 36 p., 2 plates, scale 1:100,000. [http://www.dnr.wa.gov/Publications/ger_ofr2000-4_geol_map_forks_100k.zip].

Mastin, M.C., Konrad, C.P., Veilleux, A.G., and Tecca, A.E., 2016. Magnitude, frequency, and trends of floods at gaged and ungaged sites in Washington, based on data through water year 2014 (ver 1.2, November 2017): U.S. Geological Survey Scientific Investigations Report 2016–5118, 70 p., <http://dx.doi.org/10.3133/sir20165118>.

PRISM Climate Group. 2019. Oregon State University, <http://prism.oregonstate.edu>, created 4, February 2004.

Quinault Indian Nation. 2011. WRIA-21 Salmon Habitat Recovery Strategy. June 2011 Edition. Available at: <https://www.coastsalmonpartnership.org/wp-content/uploads/2019/02/WRIA-21-Salmon-Habitat-Restoration-Strategy-June-2011-Edition.pdf>

Rieman, B.E., and J.D. McIntyre. 1993. Demographic and habitat requirements for conservation of bull trout. USDA Forest Service, Intermountain Research Station. General Technical Report INT-302.

StreamNet. 2020. Pacific Northwest salmonid and critical habitat distribution. StreamNet, Portland, Oregon. <http://www.streamnet.org/>. Accessed May 2020.

SWIFD (Statewide Washington Integrated Fish Distribution) online. 2020. http://geo.wa.gov/datasets/4ed1382bad264555b018cc8c934f1c01_0. Accessed May 2020

USBR (United States Department of the Interior, Bureau of Reclamation). 2017. SRH-2D Version 3.2.4.

USGS (United States Geological Survey). 2016. The StreamStats program, online at <http://streamstats.usgs.gov>, accessed on March 30, 2020.

Watershed Sciences. 2011. LiDAR Remote Sensing, Quinault River Basin, Washington. Delivery 2.

WDFW (Washington Department of Fish and Wildlife). 2014. Fish Passage and Diversion Screening Inventory (FPDSI): Habitat Assessment Data for Harlow Creek (WDFW ID 990548) at US 101 MP 142.48. Unpublished.

WDFW. 2019. Fish Passage and Surface Water Diversion Screening Assessment and Prioritization Manual. Olympia, Washington.

WDFW. 2020. SalmonScape. <http://wdfw.wa.gov/mapping/salmonscape>. Accessed May 2020.

Williams, R. W., and L. A. Phinney. 1975. A Catalog of Washington streams and salmon utilization. Washington Dept. of Fisheries.
http://docs.streamnetlibrary.org/WashingtonStreamCatalog/V2_Coastal/21-WRIA_QUEETS-QUINALT.pdf

WSDOT (Washington State Department of Transportation). 2017. *US 101 MP 146.85 Harlow Creek: Basis of Design Report*. Washington State Department of Transportation. Olympia, Washington.

WSDOT. 2019. *Hydraulics Manual*. Olympia, Washington. Publication M 23-03.06.

Wydoski, R., and R Whitney. 2003. Inland fishes of Washington. University of Washington Press. Seattle, Washington. 220 pp.

Yochum, S.E. 2017. *Flow Resistance Coefficient Selection in Natural Channels: A Spreadsheet Tool*. USDA. Forest Service National Stream and Aquatic Ecology Center.

DRAFT

Appendices

Appendix A: FEMA Floodplain Map (not used)

Appendix B: Hydraulic Field Report Form

Appendix C: SRH-2D Model Results

Appendix D: Streambed Material Sizing Calculations

Appendix E: Stream Plan Sheets, Profile, Details

Appendix F: Scour Calculations FHD ONLY (to be completed at FHD)

Appendix G: Manning's Calculations (not used)

Appendix H: Large Woody Material Calculations

Appendix I: WDFW Future Projections for Climate-Adapted Culvert Design

Appendix J: Bundle 3 Comment Response Plan

DRAFT

DRAFT

Appendix A: FEMA Floodplain Map

This appendix was not used because no analysis was available from FEMA in this crossing's location.

DRAFT

Appendix B: Hydraulic Field Report Form

DRAFT

**WSDOT**

Hydraulics Section

Hydraulics Field Report

Project Number:

10219302

Project Name:

Harlow Creek US 101 MP 142.48 (WDFW
990548)

Date:

7/28/2020

Project Office:

Tumwater Project Engineers Office

Time of Arrival:

9:00am

Location:

Harlow Creek US 101 MP 142.48

Time of Departure:

12:00pm

Purpose of Visit:

Site Reconnaissance

Weather:

Cloudy

Prepared By:

Rachel Ainslie

Meeting Location:

Harlow Creek, Grays Harbor County, US 101 MP 142.48

Attendance List:

Name	Organization	Role
Kristin LaForge	HDR	Water Designer
Ian Welch	HDR	Biologist
Rachel Ainslie	HDR	Water Resources EIT

Bankfull Width:


Describe measurements, locations, known history, summarize on site discussion

HDR conducted an independent site visit on July 28, 2020 to measure bankfull width, collect pebble count data, and locate a reference reach. HDR walked the stream approximately 260 feet upstream and approximately 240 feet downstream of the existing 4' span circular CMP culvert crossing. HDR took three bankfull width measurements downstream of the crossing. See Figure 1 for measurement locations.

A second site visit with HDR, WSDOT, WDFW and the tribes has not yet been conducted to gain concurrence on bankfull widths and other design considerations due to COVID-19. Table 1 summarizes bankfull measurements taken during the July 28 site visit, which were used to determine the design bankfull width. The measured bankfull widths resulted in a **design average bankfull width of 7.6 feet**.

Table 1: Bankfull width measurements

BFW #	Width (ft)	Included in Design Average	Concurrence Notes
1	7.9	Yes	No BFW concurrence meeting has occurred
2	7.4	Yes	No BFW concurrence meeting has occurred
3	7.5	Yes	No BFW concurrence meeting has occurred
Design Average	7.6		No BFW concurrence meeting has occurred



Field Data Map

US 101 Harlow Creek
To Queets River

Mile Post 142.48
WDFW ID 990548

Figure 1: Reference reach, bankfull width, and pebble count locations

Reference Reach:
<p><i>Describe location, known history, summarize on site discussion, appropriateness, bankfull measurement</i></p> <p>The reference reach is located approximately 60 feet downstream of the culvert, as shown in Figure 1 above. The reference reach is in a straight section of channel outside influence of the existing culvert and influence of LWM present in the reach. Cross section geometry in the reference reach will be used for design of the proposed channel. All three bankfull widths were taken within the reference reach. A second site visit with HDR, WSDOT, WDFW, and the tribes has not yet been conducted to gain concurrence on reference reach appropriateness. Site conditions of the reference reach where the three bankfull width measurements were taken can be viewed in Figure 21, Figure 22, and Figure 23.</p>
Data Collection:
<p><i>Describe who was involved, extents collection occurred within</i></p> <p>HDR conducted an independent site visit on July 28, 2020. HDR walked the stream approximately 260 feet upstream and approximately 240 feet downstream of the existing culvert crossing. HDR took three bankfull width measurements downstream of the culvert crossing within these extents.</p>
Observations:
<p><i>Describe site conditions, channel geomorphology, habitat type and location, flow splits, LWM location and quantity, etc.</i></p> <p>Upstream Reach</p> <p>The upstream reach observed during the site visit consisted of three different reaches: 1) Mainstem Harlow Creek from the culvert inlet to the confluence 2) Mainstem Harlow Creek above the confluence and 3) Unnamed Tributary (UNT) to Harlow Creek Left Bank. Each reach is described below and shown in Figure 1.</p> <p><i>Mainstem – Upstream of Confluence</i></p> <p>The detailed topographic survey includes 50 feet of Harlow Creek above the confluence with the UNT. The upper reach of Harlow Creek is narrow and marshy, with a substrate entirely made up of silt and fines (Figure 3). Sedges and brush are abundant on both banks. The banks are low, approximately 1 foot in height, and the channel is not well defined (Figure 4). The active floodplains are accessible, flat, and narrow; they are also terraced, and slope up to a second floodplain that appears inaccessible. The large accumulation of logs in the upper mainstem channel are the result of historic logging activities (Figure 5). At the confluence of the left bank UNT and mainstem, an accumulation of logs and sediment aggradation was observed.</p> <p><i>UNT to Harlow Creek Left Bank</i></p> <p>Detailed topographic survey of the UNT upstream extends 40 feet upstream of the confluence with Harlow Creek. At this location, a large stump lies across the channel with ferns and shrubs growing out of it (Figure 6). Flow goes under and around the stump. The channel substrate at this location is made up of fines, gravels, and some cobbles, deposited upstream of the stump (Figure 7). Downstream of the stump, the substrate is fines and organic material. The UNT channel is more defined channel than the upper reach of Harlow Creek. Both left and right banks are approximately 3 feet in height and the floodplains appear inaccessible (Figure 8). As the UNT approaches the</p>

confluence with Harlow Creek, flow goes through a narrow pinch point. LWM and a second stump are present at this pinch point.

Mainstem – Culvert Inlet to Confluence

At the approximate location where the UNT and Harlow Creek meet, an island is present in the middle of the channel. Trees grow out of the island in the middle. Small gravels and a few cobbles are present as the substrate material on either side of the island. There is a multitude of wood in the channel, all indicative of past logging (Figure 9). Both banks are about 3-4 feet in height and are vertical, and the substrate is all fines.

Where the flow converges on the downstream side of the island, there is a large log jam consisting of logs associated with historic timber harvest. Downstream of the jam, the channel narrows to approximately 5 feet wide. The substrate is mostly fines with some gravels and cobbles. Sedge and brush grow in and over the channel in this reach. The bank slopes are gradual and about 2 feet tall, made of soft material. Stands of young trees grow on the banks. The banks are undercut, and the floodplains are flat and accessible (Figure 10 and Figure 11). Natural logs help form and shore up the banks periodically.

The channel reaches a large, flat, bowl-like pool, approximately 30-40' in diameter (Figure 12). LWM from logging activities is present in the pool and racked up at the exit of the pool towards the right bank (Figure 13). The substrate of the pool is entirely fines, and the floodplains are accessible to the pool.

Past the logging wood at the exit of the pool, there is a large deposit of gravels and cobbles (Figure 14). The largest bed material found in this location was 4.5 inches in diameter. The substrate from this deposit up until the culvert inlet is primarily gravels. From this spot to the culvert approximately 50 feet away, LWM recruited naturally from the banks is present in the channel and lying across bankfull (Figure 15). The channel shape in this area consists of short vertical banks that slope up towards a flat floodplain. The banks are undercut in the proximity of the culvert (Figure 16). Natural logs shore up the banks in the stretch between the racked-up logging wood and the culvert. On the right bank near the culvert, a small side channel enters the channel. It likely carries floodplain flow from upstream to this location. There is LWM present in the side channel.

The culvert itself is a 4 foot wide CMP mitered to slope (Figure 17). The culvert inlet is perched approximately 4 inches above the channel bed.

The planform in the upstream reach of 142.48 overall is characterized by a meandering channel with a slope of approximately 1-2 percent outside of culvert backwater influence in combination with defined banks interspersed with accumulations of LWM from both past logging influences and natural recruitment that cause occasional pools and gravel deposits to form.

Downstream Reach

At the outlet of the culvert, the water level drops approximately 6 inches on to rip rap (Figure 18). Rip rap is present in the channel for 15 feet downstream of the culvert. The right bank is about 3-4 feet tall, while the left bank is lower with an accessible floodplain. Stands of trees and ferns grow on the banks. Some undercutting of the channel bank is present at a bend downstream of the rip rap. Small debris and brush is racked up after this bend; throughout the whole of the downstream reach, all LWM observed appears to be a result of natural recruitment along the banks and was not indicative of logging presence (Figure 19).

Downstream of the LWM racking, the reference reach begins (Figure 20). The left bank is slightly lower than the right, about 1-2 feet tall while the right bank is about 2-3 feet tall. The left bank floodplain is flat before sloping up to the roadway. The right floodplain is sloped. Roots of trees form the banks periodically on both banks. The channel itself is wide and flat, with no clear thalweg. All three bankfull widths were taken through this section of stream (Figure 21, Figure 22, and Figure 23). The channel substrate is gravels and cobbles, and a pebble count was performed here as well (Figure 24 and Figure 25). Trees are present on the banks and in the floodplains but there is little brush.

Downstream of the reference reach, the channel shape changes to become narrower and deeper with inaccessible floodplains (Figure 26). Both banks are 3-4 feet in height and show signs of erosion due to channel incision (Figure 27). The banks are vegetated with brush and trees, and the substrate is gravels and cobbles. Approximately 30 feet before the end of the survey extents, there is a 6 inch water drop over sedges and sediment present in the channel (Figure 28). At the very downstream end of the survey, the channel changes shape again to become wetland-like. Sedges are present in the channel.

The planform in the downstream reach of 142.48 overall is characterized by plane-bed morphology. The channel itself is flat without a defined thalweg, and the slope is approximately 2 percent.

Pebble Counts/Sediment Sampling:

Describe location of sediment sampling and pebble counts if available

During the July 2020 site visit, a Wolman pebble count was conducted downstream of the U.S. 101 culvert crossing in an area beyond the influence of the culvert, approximately 45 feet downstream of the culvert inlet and within the reference reach. See Figure 1 above for the pebble count location. Only one pebble count was conducted, sampling just over 200 particles. While counting, it was apparent from both the measurements and visual inspection that sediment throughout the surveyed reach consists of a variety of sand, gravels, and cobbles. A photo of the substrate is provided in Figure 24 and Figure 25 with a gravelometer for reference. Table 2 provides a summary of pebble count data. The results of the pebble count indicated that the bed material was composed primarily of medium to coarse gravels and small cobbles. The largest sediment size in this reach observed was 10.1 inches (0.8 foot) in diameter. See Figure 2 for the sediment size distribution observed on site.

Table 2: Sediment properties of project crossing

Sediment Size	Diameter (in)	Diameter (mm)
D₁₆	0.4	8
D₅₀	1.3	33
D₈₄	2.9	73
D₉₅	4.0	101
D₁₀₀	10.1	257




Figure 2: Pebble Count Distribution

Photos:

Any relevant photographs listed above



Figure 3: Upper Harlow Creek



Figure 4: Substrate of upper Harlow Creek



Figure 5: LWM from historic logging



Figure 6: Mid channel stump in UNT



Figure 7: Typical gravels upstream of stump



Figure 8: Typical UNT channel



Figure 9: LWM



Figure 10: Stream conditions downstream of confluence



Figure 11: Floodplains downstream of confluence



Figure 12: Large undefined bowl



Figure 13: LWM accumulation



Figure 14: Substrate downstream of LWM



Figure 15: Stream conditions between LWM and inlet



Figure 16: Incision near culvert inlet



Figure 17: Culvert inlet



Figure 18: Culvert outlet



Figure 19: Brush in channel



Figure 20: Reference reach



Figure 21: BFW 1



Figure 22: BFW 2



Figure 23: BFW 3



Figure 24: Reference reach substrate



Figure 25: Reference reach substrate (gravelometer for scale)




Figure 26: Typical channel conditions downstream of reference reach



Figure 27: Channel incising and undercut bank



Figure 28: WS drop over sedge

 Hydraulics Section	Hydraulics Field Report		Project Number:																								
	Project Name: WSDOT US 101/SR 109 Grays Harbor/Jefferson/Clallam – Remove Fish Barriers Project		Date: 6/25/2021																								
	Project Office: Olympic Region		Time of Arrival: 0900																								
	Stream Name: Harlow Creek		Time of Departure: 1100																								
WDFW ID Number: 990548	Tributary to: Queets River	Weather: Sunny																									
State Route/MP: US 101 MP 142.48	Township/Range/Section/ ¼ Section: T23N/R12W/Sec03/NE	Prepared By: Aaron Lee																									
County: Grays Harbor	Purpose of Site Visit: Data collection to support PHD revisions and FHD	WRIA: 21																									
Meeting Location: Harlow Creek (US 101 MP 142.48)																											
Attendance List:																											
<table border="1"> <thead> <tr> <th>Name</th> <th>Organization</th> <th>Role</th> </tr> </thead> <tbody> <tr> <td>Henry Hu</td> <td>Kiewit</td> <td>Stream Team Manager/SDE</td> </tr> <tr> <td>Haley Koesters</td> <td>Kiewit</td> <td>Hydraulics Engineer</td> </tr> <tr> <td>Matt Gray</td> <td>OCI</td> <td>Stream Design Engineer</td> </tr> <tr> <td>Rocky Hrachovec</td> <td>NSD</td> <td>Stream Design Engineer</td> </tr> <tr> <td>Mike Ericsson</td> <td>NSD</td> <td>Geomorphologist</td> </tr> <tr> <td>Aaron Lee</td> <td>NSD</td> <td>Hydraulic Engineer</td> </tr> <tr> <td>Olivia Vito</td> <td>NSD</td> <td>Environmental Scientist</td> </tr> </tbody> </table>				Name	Organization	Role	Henry Hu	Kiewit	Stream Team Manager/SDE	Haley Koesters	Kiewit	Hydraulics Engineer	Matt Gray	OCI	Stream Design Engineer	Rocky Hrachovec	NSD	Stream Design Engineer	Mike Ericsson	NSD	Geomorphologist	Aaron Lee	NSD	Hydraulic Engineer	Olivia Vito	NSD	Environmental Scientist
Name	Organization	Role																									
Henry Hu	Kiewit	Stream Team Manager/SDE																									
Haley Koesters	Kiewit	Hydraulics Engineer																									
Matt Gray	OCI	Stream Design Engineer																									
Rocky Hrachovec	NSD	Stream Design Engineer																									
Mike Ericsson	NSD	Geomorphologist																									
Aaron Lee	NSD	Hydraulic Engineer																									
Olivia Vito	NSD	Environmental Scientist																									
Bankfull Width:																											
<p><i>Describe measurements, locations, known history, summarize on site discussion</i></p> <p>Three bankfull width measurements were taken, three in the reference reach downstream of the culvert, measuring 9.0 feet (ft), 11.0 ft, and 11.25 ft. Bankfull width measurements performed by Natural Systems Design (NSD) were taken at locations of previous bankfull width measurements, based on the field data map in the Preliminary Design Report (PHD) and flagging identified in the field. Note that the field-measured bankfull widths in 2020 average to 7.6 ft and the PHD bankfull width is 10.3 ft. Although the reference reach selected in 2020 is fairly close to the culvert outlet and is sub-optimal in its location due to the possibility of influence by the outlet discharge, a superior reference reach was not found. Therefore, we concur with the PHD bankfull width of 10.3 ft.</p>																											
Table 1. Bankfull widths measured by NSD, including a comparison with the 2020 design average.																											
<table border="1"> <thead> <tr> <th>Station</th> <th>Bankfull Width (ft)</th> </tr> </thead> <tbody> <tr> <td>Downstream 0+75</td> <td>11.0</td> </tr> <tr> <td>Downstream 0+90</td> <td>11.25</td> </tr> <tr> <td>Downstream 1+10</td> <td>9.0</td> </tr> <tr> <td>2021 Design average</td> <td>10.4</td> </tr> <tr> <td>2020 Design average</td> <td>10.3</td> </tr> </tbody> </table>				Station	Bankfull Width (ft)	Downstream 0+75	11.0	Downstream 0+90	11.25	Downstream 1+10	9.0	2021 Design average	10.4	2020 Design average	10.3												
Station	Bankfull Width (ft)																										
Downstream 0+75	11.0																										
Downstream 0+90	11.25																										
Downstream 1+10	9.0																										
2021 Design average	10.4																										
2020 Design average	10.3																										
Reference Reach:																											
<p><i>Describe location, known history, summarize on site discussion, appropriateness, bankfull measurement</i></p> <p>The reference reach is located downstream of the crossing within the zone of hydraulic influence from the culvert and is characterized by a single thread channel that is entrenched within its banks, composed of coarse (cobble-size) bed material, and devoid of functional wood. This site is heavily impacted by human disturbances from Highway 101 located 30 ft from the left bank and intensive logging activity on the right bank and is not considered preferred as a reference reach. The upstream reach is characterized by features of a wetland bog for rearing habitat, with large</p>																											

accumulations of wood, multiple channels, low flow velocity, and undulating topography. This area is inappropriate as a reference reach due to large quantities of logging debris within the channel.

Data Collection:

Describe who was involved, extents collection occurred within

NSD conducted a site visit on July 25, 2021 with Osborn Consulting Incorporated (OCI) and Kiewit staff team members. NSD walked the stream approximately 260 ft upstream and approximately 240 ft downstream of the existing culvert crossing to identify the limits of the 2020 study. NSD collected four bankfull width measurements and two pebble counts in the upstream and downstream reaches.

Observations:

Describe site conditions, channel geomorphology, habitat type and location, flow splits, LWM location and quantity, etc.

The channel upstream of the culvert is characterized by multiple flow paths throughout an undulating mat formed by wood debris, slash, and blowdown. Flow disappears subsurface in areas. Conifers are growing throughout the area on nurse logs further splitting low flow channels. The local substrate is predominately clay with small, isolated gravel deposits downstream of large wood accumulations, which are plentiful. Confinement of the channel at the culvert inlet is likely driving local bank erosion, though the upstream reach appears relatively stable. Habitat conditions upstream of the culvert are best characterized as primarily rearing habitat with limited to no spawning opportunities. A potential site for realignment of Harlow Creek was investigated in the field, which follows a downhill gradient through a dense stand of young confers on the west side of Highway 101 (Figure 1). Field observations of compatible habitat features, potential conveyance, overall topography, connectivity to existing up- and downstream gradients, and constructability allow the potential realignment site to be feasible for additional consideration. There is insufficient data, particularly a lack of topography, to determine feasibility of a channel realignment at this time.

Downstream of the culvert the channel makes a 90-degree turn left with active bank erosion on the right bank, prior to entering the reference reach (Figure 2). Once in the reference reach, the plane bed channel has a cobble gravel substrate and is entrenched and channelized. The bed appears relatively stable, and armored given vegetation that has established on the substrate. Further downstream, the channel entrenches more deeply, with bank heights exceeding 3 ft, but has deep runs and some pools (>3 ft) created by instream wood.

Pebble Counts:

Describe location of pebble counts if available

Pebble counts were taken upstream and downstream of the culvert. The upstream pebble count was taken in the channel at station 120 ft (Photo 3). The downstream pebble count was taken in the channel within the reference reach at station 110 ft.

Table 1. Summary of grain size distribution from pebble count at downstream station 110 ft, collected by NSD in 2021. Comparison with pebble count results from 2020 is shown in the right column.

Sediment Size	2021	2020
	Downstream STA 1+10 Diameter (in)	Downstream STA 1+10 Diameter (in)
D ₁₆	0.4	0.4
D ₅₀	1.4	1.3
D ₈₄	3.0	2.9
D ₉₅	4.8	4.0
D ₁₀₀	7.1	10.1

Table 2. Summary of grain size distribution from pebble count at upstream station 120 ft, collected by NSD in 2021.


Sediment Size	2021 Upstream STA 1+20 Diameter (in)
D ₁₆	0.1
D ₅₀	0.1
D ₈₄	0.3
D ₉₅	0.8
D ₁₀₀	1.3

Photos:

Any relevant photographs listed above



Figure 1. Potential realignment site for Harlow Creek, located west of Highway 101 looking down-gradient.



Field Data Map
US 101 Harlow Creek
To Queets River
Main Post: 142.48
Width: 3.350548

Figure 2. Map of surveyed channel topography by HDR (2020). Flow direction from bottom to top of figure.



Figure 3. Location of upstream pebble count at station 120 ft.

Samples:	
Work within the wetted perimeter may only occur during the time periods authorized in the APP ID 21036 entitled "Allowable Freshwater Work Times May 2018". Work outside of the wetted perimeter may occur year-round. APPS website: https://www.govonline.wa.gov/WDFW/Public/Client/WA_WDFW/Shared/Pages/Main/Login.aspx	
Were any sample(s) collected from below the OHWM?	No <input checked="" type="checkbox"/> If no, then stop here.
	Yes <input type="checkbox"/> If yes, then fill out the proceeding section for each sample.


Sample #:	Work Start:	Work End:	Latitude:	Longitude:
Summary/description of location:				
N/A				
Description of work below the OHWL:				
N/A				
Description of problems encountered:				
N/A				

Bankfull Width Concurrence Meeting:
<p><i>Describe date and time of BFW concurrence meeting, attendees, any measurements, concurrence or decisions made that help to inform the design. You may have follow up information from this meeting and any follow up may be documented here as well.</i></p> <p>Concurrence has not been reached regarding the PHD-proposed bankfull width of 10.3 ft with WDFW. The Tribe had found a minimum hydraulic opening of 13 ft to be acceptable.</p> <p>Bankfull width concurrence meeting to agree on bankfull width has not occurred as of July 9, 2021.</p>


Appendix C: SRH-2D Model Results

DRAFT


Existing WSEL




Downstream Cross Section
STA 1+14
Existing Conditions




Downstream Cross Section
STA 1+56
Existing Conditions




Downstream Cross Section
STA 1+94
Existing Conditions




Upstream Cross Section
STA 3+18
Existing Conditions




Upstream Cross Section
STA 4+16
Existing Conditions



Upstream Cross Section
STA 4+31
Existing Conditions




Natural WSEL Profile




— Proposed Grade - - Existing Ground — 2-yr — 100-yr — 500-yr — 100-yr CC - - - XS

Upstream Cross Section
XS 4+31
Natural Conditions




Existing Ground 2-yr 100-yr 500-yr 100-yr CC

Upstream Cross Section
XS 4+15
Natural Conditions




Existing Ground 2-yr 100-yr 500-yr 100-yr CC

Upstream Cross Section
XS 3+19
Natural Conditions




Existing Ground Natural Grade 2-yr 100-yr 500-yr 100-yr CC

Structure Cross Section
XS 2+65
Natural Conditions




— Natural Grade — 2-yr — 100-yr — 500-yr — 100-yr CC

Downstream Cross Section
XS 1+94
Natural Conditions




Existing Ground Natural Grade 2-yr 100-yr 500-yr 100-yr CC

Downstream Cross Section
XS 1+55
Natural Conditions




Existing Ground 2-yr 100-yr 500-yr 100-yr CC

Downstream Cross Section
XS 1+14
Natural Conditions




Existing Ground 2-yr 100-yr 500-yr 100-yr CC

Proposed WSEL Profile




Upstream Cross Section
XS 4+31
Proposed Conditions




Existing Ground 2-yr 100-yr 500-yr 100-yr CC

Upstream Cross Section
XS 4+15
Proposed Conditions




Existing Ground 2-yr 100-yr 500-yr 100-yr CC

Upstream Cross Section
XS 3+19
Proposed Conditions




Existing Ground Proposed Grade 2-yr 100-yr 500-yr 100-yr CC

Structure Cross Section
XS 2+65
Proposed Conditions




Proposed Grade 2-yr 100-yr 500-yr 100-yr CC Structure Walls

Downstream Cross Section
XS 1+94
Proposed Conditions




— Proposed Grade - - Existing Ground — 2-yr — 100-yr — 500-yr — 100-yr CC

Downstream Cross Section
XS 1+55
Proposed Conditions




Existing Ground 2-yr 100-yr 500-yr 100-yr CC


Downstream Cross Section
XS 1+14
Proposed Conditions



Existing Ground 2-yr 100-yr 500-yr 100-yr CC




WATER SURFACE ELEVATION




DEPTH




VELOCITY




SHEAR



EXISTING CONDITIONS 2-YEAR




WATER SURFACE ELEVATION




DEPTH




VELOCITY




SHEAR



EXISTING CONDITIONS 100-YEAR




WATER SURFACE ELEVATION




DEPTH




VELOCITY




SHEAR




EXISTING CONDITIONS 500-YEAR




Velocity



WSEL




Depth




Shear


2-year Natural Conditions




Velocity



WSEL




Depth




Shear


100-year Natural Conditions




Velocity



WSEL




Depth




Shear


500-year Natural Conditions




Velocity



WSEL




Depth




Shear


100-year CC Natural Conditions




Velocity



WSEL




Depth




Shear


2-year Proposed Conditions




Velocity



WSEL




Depth




Shear


100-year Proposed Conditions




Velocity



WSEL




Depth




Shear


500-year Proposed Conditions




Velocity



WSEL



Depth




Shear

100-year CC Proposed Conditions

Appendix D: Streambed Material Sizing Calculations

DRAFT

Sediment Gradation Streambed Design



Fuller-Thompson Gradation

Dmax = 10

D[in]

18.000 130.28

15.000 120.02

12.000 108.55

10.000 100.00

8.000 90.45

6.000 79.46

5.000 73.20

4.000 66.21

3.000 58.17

2.500 53.59

2.000 48.47

1.500 42.58

1.000 35.48

0.750 31.17


No. 4 = 16.69

No. 40 = 5.63

No. 200 = 2.58

Summary - Meander Bar Material Design										Streambed Mobility/Stability Analysis									
Project:		Site 17 PHD Rev 1.0 (MP 142.48, Harlow Cr)								References:									
By:		Aaron Lee								Stream Simulation: An Ecological Approach to Providing Passage for Aquatic Organisms at Road-Stream Crossings									
										Appendix E--Methods for Streambed Mobility/Stability Analysis									
										Limitations:									
										D ₈₄ must be between 0.40 in and 10 in									
										uniform bed material (D _i < 20-30 times D ₅₀)									
										Slopes less than 5%									
										Sand/gravel streams with high relative submergence									
										γ _s		165 specific weight of sediment particle (lb/ft ³)							
										γ		62.4 specific weight of water (lb/ft ³)							
										τ _{D50}		0.054 dimensionless Shields parameter for D50							
										Flow		2-YR (38 cfs) 100-YR (91 cfs) 2080 100-YR (113.2 cfs) 500-YR (110 cfs)							
										Average Modeled Shear Stress (lb/ft ²)		1.3 2.0 2.2 2.2							
										τ _{ci}									
										3.09		No Motion No Motion No Motion No Motion							
										2.98		No Motion No Motion No Motion No Motion							
										2.86		No Motion No Motion No Motion No Motion							
										2.70		No Motion No Motion No Motion No Motion							
										2.51		No Motion No Motion No Motion No Motion							
										2.37		No Motion No Motion No Motion No Motion							
										2.22		No Motion No Motion No Motion No Motion							
										2.10		No Motion No Motion Motion Motion							
										1.97		Motion Motion Motion Motion							
										1.80		Motion Motion Motion Motion							
										1.71		Motion Motion Motion Motion							
										1.60		No Motion Motion Motion Motion							
										1.46		No Motion Motion Motion Motion							
										1.39		No Motion Motion Motion Motion							
										1.30		Motion Motion Motion Motion							
										1.19		Motion Motion Motion Motion							
										1.05		Motion Motion Motion Motion							
										0.97		Motion Motion Motion Motion							
												Mix Size							
										D16		0.6 in							
										D50		3.3 in							
										D50		0.3 ft							
										D84		13.2 in							
										D95		16.5 in							

Sediment Gradation Meander Bars



Fuller-Thompson Gradation

Dmax = 18

D[in]

18.000 100.00

15.000 92.12

12.000 83.32

10.000 76.76

8.000 69.43

6.000 61.00

5.000 56.19

4.000 50.82

3.000 44.65

2.500 41.13

2.000 37.20

1.500 32.69

1.000 27.23

0.750 23.93

No. 4 = 12.81

No. 40 = 4.32



No. 200 = 1.98

Appendix E: Stream Plan Sheets, Profile, Details

DRAFT

T.24N. R.12W. W.M.

LEGEND	
EXISTING STREAM ALIGNMENT	56
EXISTING INDEX CONTOUR	250
EXISTING INTERMEDIATE CONTOUR	
STREAM SCALABLE EDGE	
EXISTING EDGE OF PAVEMENT	



PRELIMINARY - NOT FOR CONSTRUCTION








FILE NAME		c:\users\rhaddeland\pw_wsdot\0256430\XL6147_PS_CE_001.dgn																			
TIME	10:44:52 AM					REGION NO.	STATE	FED.AID PROJ.NO.													
DATE	6/8/2020					10	WASH														
PLOTTED BY	RHADDELAND					JOB NUMBER		XXXXXX													
DESIGNED BY	S. BEVAN					CONTRACT NO.			LOCATION NO.												
ENTERED BY	C. WILCOX							XL6147													
CHECKED BY	J. HEILMAN																				
PROJ. ENGR.	X. XXXXXX																				
REGIONAL ADM.																					
		REVISION		DATE		BY															


</

p:\H\Q\LYMAPPP\03P.WSDOT\LOC\WSDOT\Documents\HQ\Fish Passage\ORproj\101142.48_HarlowC.TribtoQueetsRiv\Hydraulics\CAD_Sheets\XL6147_PS_CE_001.dgn

T.24N. R.12W. W.M.




LEGEND	
NEW STREAM ALIGNMENT	
EXISTING INDEX CONTOUR	
EXISTING INTERMEDIATE CONTOUR	
STREAM SCALABLE EDGE	
EXISTING EDGE OF PAVEMENT	
CUT LINE	
FILL LINE	



NOTES:


1. SLOPES SHOWN OUTSIDE HYDRAULIC OPENING ARE FOR ILLUSTRATIVE PURPOSES ONLY TO DEPICT ESTIMATED AREA OF POTENTIAL IMPACT. FINAL AREAS OF IMPACT TO BE DETERMINED PENDING GEOLOGICAL AND STRUCTURAL INVESTIGATION, STRUCTURE TYPE, AND STRUCTURE LOCATION.
2. PROPOSED STRUCTURE SHOWN FOR ILLUSTRATIVE PURPOSES ONLY. STRUCTURE TYPE, SIZE, AND LOCATION TO BE DETERMINED DURING LATER PHASE OF DESIGN. PROPOSED STRUCTURE SHALL NOT ENCROACH INTO HYDRAULIC OPENING SHOWN ON PLAN.
3. LIDAR DATA WAS USED IN LOCATIONS WHERE DAYLIGHT LIMITS EXTEND BEYOND DETAILED SURVEY.




PRELIMINARY - NOT FOR CONSTRUCTION

FILE NAME		\$\$\$\$\$\$\$DESIGNFILENAME\$\$\$\$\$																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
-----------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

p:\H00LYMAPPPW03P.WSDOT.LOC\WSDOT\Documents\HQ\Fish Passage\ORproj\101142.48_HarlowCrTriboQueetsRiv\Hydraulics\CAD\ Sheets\XL6147_PS_PR_CP_001.dgn



FILE NAME\$\$\$\$\$\$\$DESIGNFILENAME\$\$\$\$\$														 Washington State Department of Transportation		US 101 MP 142.48		PLAN REF. NO.	
TIME\$TIMES					REGION NO.	STATE	FED.AID PROJ.NO.						CP1						
DATE\$\$\$\$DATE\$\$\$					10WASH														
PLOTTED BY \$\$USERNAME\$																			
DESIGNED BY M. HRACHOVEC					JOB NUMBER														
ENTERED BY G. DORAN					XXXXX														
CHECKED BY A. LEE					CONTRACT NO.														
PROJ. ENGR. X. XXXXXXXX							LOCATION NO. XL6147												
REGIONAL ADM.		REVISION		DATE	BY					DATE		DATE				SHEET 3 OF 4 SHEETS			
										P.E. STAMP BOX		P.E. STAMP BOX				STREAM PROFILE			



SECTION B



SECTION B

PRELIMINARY - NOT FOR CONSTRUCTION

- PRELIMINARY - NOT FOR CONSTRUCTION**



Appendix F: Scour Calculations

This appendix was not used because it is used for the FHD Report, not the PHD Report.

DRAFT

Appendix G: Manning's Calculations

This appendix was not used because Manning's calculations were not needed to support the values chosen.

DRAFT

Appendix H: Large Woody Material Calculations

DRAFT

WSDOT Large Woody Material for stream restoration metrics calculator

State Route# & MP	Hwy 101 MP 142.48	Key piece volume	1.310 yd ³
Stream name	Harlow Cr	Key piece/ft	0.0335 per ft stream
length of regrade ^a	145.5 ft	Total wood vol./ft	0.3948 yd ³ /ft stream
Bankfull width	10.3 ft	Total LWM ^c pieces/ft stream	0.1159 per ft stream
Habitat zone ^b	Western WA		

Log type	Diameter at midpoint (ft)	Length(ft) ^d	Volume (yd ³ /log) ^d	Rootwad?	Qualifies as key piece?	No. LWM pieces	Total wood volume (yd ³)	DBH based on mid point diameter (ft)
A	2.00	33	3.84	yes	yes	8	30.72	2.14
B	1.67	30	2.43	no	yes	10	24.34	1.90
C	1.33	30	1.54	no	yes	4	6.17	1.56
D			0.00	yes			0.00	
E			0.00	no			0.00	
F			0.00				0.00	
G			0.00				0.00	
H			0.00				0.00	
I			0.00				0.00	
J			0.00				0.00	
K			0.00				0.00	
L			0.00				0.00	
M			0.00				0.00	
N			0.00				0.00	
O			0.00				0.00	
P			0.00				0.00	

	No. of key pieces	Total No. of LWM pieces	Total LWM volume (yd ³)
Design	22	22	61.2
Targets	5	17	57.4

Appendix I: Future Projections for Climate-Adapted Culvert Design

DRAFT

Future Projections for Climate-Adapted Culvert Design

Project Name: 990548

Stream Name: Harlow Creek

Drainage Area: 180 ac

Projected mean percent change in bankfull flow:

2040s: 20.4%

2080s: 26.6%

Projected mean percent change in bankfull width:

2040s: 9.7%

2080s: 12.5%


Projected mean percent change in 100-year flood:

2040s: 19.4%


2080s: 24.2%



Projected percent change in bankfull width



Projected percent change in 100-year flow



Black dots are projections from 10 separate models

The Washington Department of Fish and Wildlife makes no guarantee concerning the data's content, accuracy, precision, or completeness. WDFW makes no warranty of fitness for a particular purpose and assumes no liability for the data represented here.

Appendix J: Bundle 3 Comment Response Plan

DRAFT

4.0 Comments and Responses – Bundle 3, Site 17 (#990548)

WDFW NUMBER:		PROJECT NAME	DATE OF REVIEW
990548		Harlow Creek - US 101 MP 142.48	10/2/2020
CONTACT PHONE:		PROJECT CONTACT:	COMMENT DUE DATE
		Nick Harvey - Harveni@wsdot.wa.gov	
REVIEWER PHONE:		REVIEWERS NAME:	REVIEWERS ORGANIZATION:
(360) 640-5283		Lauren Macfarland	Quinault Indian Nation
COMMENT #	PAGE/SHEET	REVIEWERS COMMENT	DESIGNERS COMMENTS
1		While I did measure larger BFW at this site than was surveyed in PHD, I concur with PHD that the hydraulic opening is sufficiently large to accommodate the large amounts of LWM found along this stream.	We concur with the bankfull width of 10.3 ft and minimum hydraulic opening of 15 ft.

WDFW Review Comments on WSDOT Preliminary Hydraulic Design Report	WDFW Site ID: <u>990548</u> Stream Name: <u>Harlow Creek</u> US/SR <u>101</u> MP <u>142.48</u>	Comments By: Gina Piazza Pat Klavas 10/7/20	<u>Limit Comments limited to does not meet:</u> 2013 Water Crossing Design Guidelines, <u>Or</u> Stream Design Checklist <u>Or</u> Relevant WAC

No.	PHD Page	Topic	Comment with Citations from 2013 WCDG, Stream Design Checklist, or WAC	Stream Team Response
1	10, 26, 28, 60	Channel Shape	WDFW measured an average BFW of 12.7'. WDFW recommends a larger minimum hydraulic opening. Cross sections should reflect this 12.7' BFW with banks and high flow benches.	n/a
2	18	Associated Materials	Riprap and other associated materials must be removed from the channel.	Agreed, removal of riprap will be addressed in the FHD.
3	68, 76	Climate change	WDFW recommends using predicted BFW to achieve a climate adapted structure. This will take into account fish habitat and the change to lower flow conditions which fish use.	Comment interpreted as preference, not requirement. If this is a mistake, please let WSDOT know. WSDOT has provided WDFW with the WSDOT climate change policy. This policy was followed for the PHD.
4	69	Freeboard	Freeboard appears small based upon the need to pass all expected wood and sediment in this system.	The proposed freeboard of 6 ft is considered adequate. The functional wood pieces present in the upstream reach are remnants from historical logging activity and are not mobile. Furthermore, the upstream

				reach is defined by characteristics typical of a wetland bog; low flow velocity through undulating topography and accumulations of debris and lacking the stream power to transport large wood pieces downstream.
5	72	Wood placement	Wood placement function appears more as bank protection rather than channel habitat and complexity. Consider re-evaluating placement locations.	Wood placement will be re-evaluated prior to development of the JARPA submittal, including size, position, and intended habitat and geomorphic function. Wood placement in the reach downstream of the culvert will consider the long-term degradation potential and habitat benefit.
6	77	Long Term Degradation	Is the 1-3 feet long term degradation upstream or through the crossing? Will the channel become incised or affect the slope ratio?	Field observations indicate the upstream reach is in a degraded state, but relatively stable. Large pieces of immobile wood will continue to provide grade control in the upstream reach. Localized erosion at the channel inlet is a result of confinement at the culvert inlet, and not typical of the project reach. Channel incision (1-3 ft) is not expected to result from the proposed increase in hydraulic opening. Historic downstream degradation appears to be stabilizing vertically as evidenced by moss-covered cobble providing grade control in the downstream end of the reference reach.
7	CR1	alignment	Consider improving alignment to reduce the downstream bend.	Lengthening the radius of curvature in the reach immediately downstream of the culvert was evaluated in the PHD, and it was determined to use the current alignment for the proposed channel design. The downstream bend does not locally increase flow velocity and is not identified as a significant risk for lateral channel migration. Note that the proposed design will provide LWM at the downstream bend to provide additional hydraulic complexity and habitat features.

8	CD1	Section A	Section A cross section appear to be raising and confining the channel. Consider working with the existing topography.	Proposed channel geometry and grade has been evaluated. The proposed design of cross-section A is intended to develop a low-flow notch along its thalweg in the short to medium term following construction. This self-driving process will connect the existing channel topography upstream with the graded section downstream along the thalweg.
---	-----	-----------	--	--

In addition to your comments above, please respond to the following questions even if the response may duplicate comments previously entered in the table.

- Based on the information available and on previous discussions, does the design of the project, considering it is at this draft level of completeness, follow the guidelines included in WDFW's Water Crossing Design Guidelines? If "no", reference the number of the comment(s) in the response table above that address instances where WDFW guidelines are considered not followed.
Yes, if comment 1 is addressed adequately.
- Based on the information available and on previous discussions, do you foresee problems with this project receiving an HPA? If "yes", reference the number of the comment(s) in the response table above that address instances where these requirements are considered not followed.
No, if comments are addressed adequately.
- Does the PHD bankfull width match the expected value based on site visits, prior measurements, or derived from other described methods? If "no", list the expected bankfull width to be used for design or reference comment number in the table above that discusses expected bankfull width.
~~No, WDFW measured 12.7'.~~
- Does the minimum span of the replacement structure match or exceed the minimum value expected by the reviewer? If "no", reference the number of the comment(s) in the response table above that address structure span being different than expected.
~~No, see above.~~